

1060164

TO: STATE CORPORATION COMMISSION

7-15

API NUMBER 15-055-20,581.0000
C SE NW SEC. 8 T 21 S, R 33 W

CONSERVATION DIVISION - PLUGGING SECTION 3300 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3300 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME WAMPLER WELL # A-1

TECHNICIAN'S PLUGGING REPORT COUNTY FINNEY

OPERATOR LICENSE # 4058 WELL TOTAL DEPTH 4825 156.81 FEET

OPERATOR: AMERICAN WARRIOR PRODUCTION CSG: SIZE 5 1/2" @ 4661' WITH 200 SX

NAME AND PO BOX 399 SURFACE CASING: SIZE 8 5/8" @ 370' WITH 250 SX

ADDRESS GARDEN CITY, KS 67846

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SWIFT SERVICES, INC LICENSE NUMBER 32382

ADDRESS PO BOX 466, NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 12:30 PM DAY: 15 MONTH: 07 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM TED

(COMPANY NAME) SWIFT SERVICES, INC (PHONE) 785-798-2300

WERE: PERFS AT 4430-38 DV TOOL @ 2130 WITH 450 SX CEMENT

BOTTOM PLUG PUMP 30 SX CEMENT AND 300# HULLS.

PUMP 19 SX GEL AND 185 SX CEMENT DOWN CASING. PRESSURED TO 700#. SHUT IN WITH 100#.

WENT DOWN BACKSIDE WITH 10 SX CEMENT AND PRESSURED TO 500#.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:15 PM DAY: 15 MONTH: 07 YEAR: 1999

ACTUAL PLUGGING REPORT

BOTTOM PLUG PUMP 30 SX CEMENT AND 300# HULLS.

PUMP 19 SX GEL AND 185 SX CEMENT DOWN CASING. PRESSURED TO 700#. SHUT IN WITH 100#.

WENT DOWN BACKSIDE WITH 10 SX CEMENT AND PRESSURED TO 500#.

RECEIVED
STATE CORPORATION COMMISSION
7-26-99
JUL 26 1999

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED
Conservation Division
Wichita, Kansas

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE 7-28-99

SIGNED Michael J Maier (TECHNICIAN) FORM CP-2/3

INV. NO. 60079

(2)