

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-01003-00-01
Spot: CSWSW Sec/Twnshp/Rge: 8-21S-33W
660 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: WAMPLER OWWO Well Number: 2
County: FINNEY Total Vertical Depth: 2807 feet

Operator License No.: 32281
Op Name: GMX RESOURCES, INC.
Address: 9400 N. BROADWAY STE 600
OKLAHOMA CITY, OK 73114

Conductor Pipe: Size _____ feet: _____
Surface Casing: Size 8.625 feet: 258 WITH 250 SX CMT
Production: Size 4.5 feet: 2806 WITH 1250 SX CMT
Liner: Size _____ feet: _____

91.23

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/23/2001 10:45 AM

Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.

Proposal Rcvd. from: HAROLD WRIGHT Company: SWIFT SERVICES, INC. Phone: (785) 798-2300

Proposed Plugging Method: PUMP DOWN 4 1/2" CASING WITH 400# HULLS. CMT TO SURFACE. BRING 50 SX CMT FOR BACKSIDE. TEST TO 500#.

Plugging Proposal Received By: SCOTT ALBERG
Date/Time Plugging Completed: 04/23/2001 11:45 AM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: KEVIN STRUBE

Actual Plugging Report:

PBTD 2770'. PERFS AT 2578-2704'. PUMPED DOWN 4 1/2" CASING 165 SX CMT. WELL ON VACUUM. SHUT IN. PUMPED DOWN 8 5/8" X 4 1/2" ANNULUS 5 SX CMT. PRESSURED UP TO 250#. BLEW HOLE @ BRAIDEN HEAD. WELL STAYED LOADED. TOPPED OFF 4 1/2" CASING WITH 15 SX CMT. STAYED AT SURFACE.

INVOICED
DATE 4-27-01
WELL NO. 2001061729

RECEIVED
STATE CORPORATION COMMISSION
APR 27 2001

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

Plugged through: CSG

CONSERVATION DIVISION
Wichita, Kansas
4-27-01

District: 01

Signed Kevin D Strube
(TECHNICIAN)

APR 26 2001

MP

Form CSG