

To: 1 120557
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-22 API NUMBER 19-185-22,765.0000 424 R

SE NW NW, SEC. 32, T. 21 S, R. 14 W/X
4290 feet from S section line
4290 feet from E section line
Lease Name Neeland Well # 1
County Stafford 126.75
Well Total Depth 3900 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 445

TECHNICIAN'S PLUGGING REPORT

Operator License # 5822
Operator: Val Energy Inc.
Name & Address: Box 322
Haysville, KS 67060

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Val Energy Inc. License Number 5822

Address Box 322, Haysville, KS 67060

Company to plug at: Hour: 5 a.m. Day: 22 Month: 4 Year: 19 91

Plugging proposal received from Skip Smith

(company name) Val Energy Inc. (phone) 316-522-1560

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 906'

1st plug at 3800' with 40 sx cement, 2nd plug at 930' with 50 sx cement,

3rd plug at 470' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 7:30 a.m. Day: 22 Month: 4 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 3800' with 40 sx cement,

2nd plug at 930' with 50 sx cement,

3rd plug at 470' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 5-13-91

INV. NO. 31806

Signed Duane Rankin (TECHNICIAN)

EFFECTIVE DATE: 4-15-91

FORM MUST BE TYPED
FORM C-1 4/90

State of Kansas 15-185-22,765.0000

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 4-15-91
month day year

SE NWNW 32 21 14W East
Sec Twp S, Rg X West

OPERATOR: License # 5822
Name: VAL ENERGY, INC
Address: Box 322
City/State/Zip: Haysville, Ks 67060
Contact Person: K. Todd Allam
Phone: 316-522-1560

4290 feet from South line of Section
4290 feet from East line of Section
(Note: Locate well on Section Plat on Reverse Side)

CONTRACTOR: License #: 5822
Name: Val Energy, Inc.

County: Stafford
Lease Name: Neeland Well #: 1
Field Name: Unknown

Well Drilled For: Well Class: Type Equipment:
X Oil Inj Infield X Mud Rotary
Gas Storage Pool Ext. Air Rotary
OWWO Disposal X Wildcat Cable
Seismic; # of Holes

Is this a Prorated Field? yes X no
Target Formation(s): Arbuckle
Nearest lease or unit boundary: 990
Ground Surface Elevation: 1950 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 110
Depth to bottom of usable water: 200
Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 220
Length of Conductor pipe required: 3950

If OWWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Formation at Total Depth: Arbuckle
Water Source for Drilling Operations:
well X farm pond other

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location:

DWR Permit #:
Will Cores Be Taken? yes X no
If yes, proposed zone:
220' Alt. I Req.

Exp. 10/10/91

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Pusher Smith
SPUD DATE 4-16-91 INIT. RR
LENGTH SURFACE PLANNED 300 +
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 2 1/2" 445 CONDUCTOR
ANHYDRITE T- B-906 ELEVATION
TD- 3900 FORMATION
RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 3800 Ft. W/ 40 SX
1/2 Base Anyh. @ 930 Ft. W/ 50 SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ 470 Ft. W/ 50 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 1 1/2 SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond Hauling)
TECHNICIAN RR DATE
TYPE OF CEMENT 60/40 6% gel
STARTING TIME 5: (AM/PM) DATE 4-22-91
COMPLETION TIME 7:30 (AM/PM) DATE 4-22-91
CEMENT COMPANY Hall
Dumas saw