

7-11 15.185.10822.0000

120277

API NUMBER 15- Drill Completion Date 9/29/56

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE SW SE, SEC. 32, T 21 S, R 14 WXE  
330 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6939

Lease Name Bauer Well # 2

Operator: Chapman Exploration, Inc.  
Name & Address: 6100 South Yale, Suite 1816  
Tulsa, OK 74136

County Stafford

Well Total Depth 3860 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 280

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Klima Well Service License Number 7023

Address 610 West Front, P.O. Box 386, Claflin, KS 67525

Company to plug at: Hour: 9 a.m. Day: 11 Month: 7 Year: 19 89

Plugging proposal received from Vernon Klima

(company name) Klima Well Service (phone) 316-587-3570

were: 5 1/2" at 3842' CIBP at 3800' Hole in 5 1/2" casing at 1360'

1st plug sand 5 1/2" casing back to 3700' with 5 sx cement on top of sand through bailer,

2nd plug run tubing to 1400' and circulate cement. If cement does not circulate behind 5 1/2" casing, squeeze cement in 8 5/8" & 5 1/2" annulus.

RECEIVED

JUL 24 1989

6-24-89

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3 p.m. Day: 11 Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3700' and dumped 5 sx cement on top of sand through bailer,

2nd plug ran tubing to 1417' and pumped 385 sx cement, cement did not circulate. Pulled tubing to 708' and circulated cement with 50 sx cement.

3rd plug pumped 200 lbs. hulls and 110 sx cement down 8 5/8" & 5 1/2" annulus. No pressure on vacuum. Cut off 5 1/2" & 8 5/8" and filled with 2 1/2 yards Ready Mix cement on 7/17/89. Plug slipped 225'.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. No casing recovery.  
(if additional description is necessary, use BACK of this form.)

INVOICE observe this plugging.

DATE 7-25-89

Signed [Signature] (TECHNICIAN)

INV. NO. 25397