

1 010247

15.185.21088.0000

6-5-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 7425

Operator: Robert Guthrie
Name & Address 2650 North Main
Great Bend, KS 67530

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10:25 a.m. Day: 5 Month: 6 Year: 1987

Plugging proposal received from Mike Gomez

(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 3858' Perfs at 3650-54'

1st plug sand back to 3600' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 2'sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, and 125 sx cement.

Plugging Proposal Received by Paul Luthi and Jack Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:55 a.m. Day: 5 Month: 6 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sanded back to 3600' and dumped 4 sx cement on top of sand
through bailer,

2nd plug pumped 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, and 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 9 - 1987 6-9-87

Maximum pressure 700 psi and shut in 150 psi.

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 1876' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-9-87

INV. NO. 17199

6-5

Signed Jack Luthi
(TECHNICIAN)



Mike Hayden
Michael Lennen
Margalee Wright
Keith R. Henley
Judith A. McConnell
Brian J. Moline

Governor
Chairman
Commissioner
Commissioner
Executive Secretary
General Counsel

State Corporation Commission
CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286
Ph. 316-263-3238

THIS NOTICE

JUN 30 '87

EXPIRES

March 30, 1987

WELL PLUGGING NOTICE

Marker B #1
C NE NE
Sec. 32-21S-14W
Stafford County

Robert Guthrie
2650 N. Main
Great Bend, KS 67530

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

Jack McCord, Director

Please contact the district office to review your suggested method of plugging
DIST. #1 302 West McArtor, Dodge City, KS 67801 (316) 225-6760
five days prior to plugging the well (KAR-82-3-113).