

7-11 15.185.00594.0001

Docket #E-16,232

To: 1 120278
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 12/2/56

NE SE SE, SEC. 32, T 21 S, R 14 W/E
990 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6939

Lease Name Bauer Well # 4
County Stafford 134.06

Operator: Chapman Exploration, Inc.
Name:
Address 6100 South Yale, Suite 1816
Tulsa, OK 74136

Well Total Depth 4125 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 284

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Chapman Exploration, Inc. License Number 6939
Address 6100 South Yale, Suite 1816, Tulsa, OK 74136

Company to plug at: Hour: 3:30 p.m. Day: 11 Month: 7 Year: 19 89

Plugging proposal received from Jim Cartledge
(company name) Chapman Exploration (phone) 316-793-5936

were: 5 1/2" at 3904' CIBP at 3674' & 3586' Perfs at 3848-72' & 3557-67'

1st plug pump down 5 1/2" with 3 sx hulls, 30 sx cement, gel spacer up to base in anhydrite,
fill with cement from anhydrite base to surface,

2nd plug pump 125 sx cement down 8 5/8" & 5 1/2" annulus.

Plugging Proposal Received by Stephen J. Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4:30 p.m. Day: 11 Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped in 5 1/2" casing with 150 lbs. hulls, 50 sx cement,
15 sx gel, 50 lbs. hulls, and 110 sx cement. Pumping pressure 0-500 psi and shut in 150 psi.

2nd plug pumped between 8 5/8" surface casing & 5 1/2" casing with 125 sx cement. Pumping
pressure 0-200 psi and shut in 100 psi.

Cut off 5 1/2" & 8 5/8" and filled with 2 yards of Ready Mix cement on 7/17/89. RECEIVED

Plugs slipped 235'. STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. No casing recovery. 1111 7 9 1989

(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 7-20-89
INV. NO. 25378

CONSERVATION DIVISION
Wichita, Kansas

Signed [Signature] 7-19-89
(TECHNICIAN)