

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-03406-00-00
Spot: CSWSWNE Sec/Twnshp/Rge: 27-16S-12W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: W W PENKA A Well Number: 1
County: BARTON Total Vertical Depth: 3384 feet

Operator License No.: 101
Op Name: KCC FEE FUND
Address: 130 S. MARKET, ROOM 2078
WICHITA, KS 67202

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 285
Production: Size 5.5 feet: 3377
Liner: Size _____ feet:

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/26/2002 6:00 PM
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC
Proposal Rcvd. from: EDWARD POE Company: POE SERVICING INC Phone: (785) 475-3422

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 10% gel - 400# hulls.
Perforated casing at 1500' - 800' - 425'.

Plugging Proposal Received By: HERB DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/30/2002 12:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Poe Servicing Inc. RIH with tubing at 6:00 P.M. on 09-26-2002 with Jay Pfeifer and pumped 200 sxs 60/40 pozmix.
Poe Servicing Inc. pulled the tubing.
09/27/2002 - Poe Servicing Inc. ran back in the hole and tagged cement at 1300'.
Ordered 300 sxs cement and 400# hulls.
Pumped 200 sxs cement with 400# hulls to circulate cement to surface.
Pulled tubing - tied onto backside and pumped 20 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.
Left well set for 2.5 hours.
Pumped the 80 sxs cement into casing - well was not full.
09-30-2002 - Tied onto casing and pumped 15 sxs to fill casing to capacity.
Job complete.

RECEIVED
KANSAS CORP COMM
2002 OCT -4 1:29

10-4-02

Remarks: ALLIED CEMENTING COMPANY-TICKET #13151 AND #13101.

Plugged through: TBG

District: 04

Signed *Pat Staab*
(TECHNICIAN)

OCT 01 2002

C. E. ASH ET AL #1 W. W. BENKA 'A' 27-16-12W
SW SW NE

Contr. BARTON County

E. 1912 Comm. 9-10-15 Comp. 9-27-15 IP. 205 EOPD

Tops	Depth	Datum
ANHY	790	
LANS	3093	
S CONG	3360	
ARB	3376	
TD	3384	

Casing
8" 285
5" 3377

A/500
SSO 3110-17
700' OIH/8 hr

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS