

7-29

To: 6 070708  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 009-23,671-00-00  
SE NW SE, SEC. 27, T 16s, R 12 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5928 STATE CORPORATION COMMISSION  
10-21-88  
OCT 21 1988

Operator: Duke Drilling Co. Inc.  
Name & Address: 620 Hubbard Box 823  
Great Bend, Ks. 67530  
Dorothy M. Hague

Lease Name McLaughlin Well # 9  
County Barton 111.05  
Well Total Depth 3417 feet  
Conductor Pipe: Size 0 feet  
Surface Casing: Size 8 5/8 feet 255

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. and DS and W License Number  
Address Great Bend, and Claflin, Ks.

Company to plug at: Hour: PM Day: 29 Month: July Year: 19 88

Plugging proposal received from Leonard Williamson and Keith Lumkins

(company name) Duke Drilling and Lumkin Oil (phone)

were: 8 5/8" - 255' S.P. cwc w/160 sks. 5 1/2" casing set at 3416' w/125 sks cement.

Perf at 3359' at bottom Rockhold Eng. Sanded 5 1/2" casing to 3300' and w/5 sks cement casing 5 1/2" parted at 300'. Proposal perf at 780'. Run tubing to anhy and circulate cement.

Then, squeeze 8 5/8" S.P. with cement. Shut in under pressure. Order 250 sks 65/35 Poz 6% Gel and 5 sks Hulls.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 6:15PM Day: 29 Month: July Year: 19 88

ACTUAL PLUGGING REPORT Ordered 250 sks 65/35 Poz 6% Gel and 2 sks Hulls. Spotted with

tubing, pumped in with pump truck. 1. Ran tubing to 454.77' (bit froze) Cement circulated out of 5 1/2" casing with 100 sks cement. 2. Squeezed 8 5/8" S.P. with 150 sks cement.

Max pressure 500 psig. Shut in at 250 psig. Cemented by Allied Cement Co.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED  
DATE 10-24-88  
INV. NO. 22671

Signed Marion J. Schmidt (TECHNICIAN)  
Marion J. Schmidt