

WELL PLUGGING RECORD

15-145-20872-0000

Give All Information Completely  
 Make Required Affidavit

COUNTY Pawnee SEC. 1 TWP. 23S RGE. 17W E/W  
 Location as in quarters or footage from lines:  
1320' FNL; 330' FWL, NW/4


Lease Owner Lebsack Oil Production, Inc.  
 Lease Name White #1 Well No. 1  
 Office Address P. O. Box 489, Hays, Kansas 67601  
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
 Date Well Completed November 26, 1981  
 Application for plugging filed November 25, 1981  
 Plugging commenced 12:15 AM November 26, 1981  
 Plugging completed 2:00 AM November 26, 1981  
 Reason for abandonment of well or producing formation Dry Hole

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4260'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	257'	None

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud.  
 70 sacks 50/50 Pozmix with 4% gel and 3% cc at 660';  
 40 sacks at 270'; Bridge with 10 sacks at 40' to  
 surface, 10 sacks in rathole; 5 sacks in mousehole;  
 5 sacks in water well.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company, P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS COUNTY OF RICE, ss.

F. A. Wuellner (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

STERLING DRILLING COMPANY  
 (Signature) F. A. Wuellner  
 F. A. Wuellner, Secretary  
 P. O. Box 129, Sterling, Kansas  
 (Address) 67579

SUBSCRIBED AND SWORN TO before me this 30th day of November, 19 81.



Agnes D. Wurst  
 Agnes D. Wurst, Notary Public

My Commission expires: \_\_\_\_\_

RECEIVED  
 STATE CORPORATION COMMISSION

DEC - 5 1981

CONSERVATION DIVISION  
 Wichita, Kansas

12-3-81

STERLING DRILLING COMPANY  
P. O. Box 129  
Sterling, Kansas 67579

15-145-20872-0000

WELL LOG ----- WHITE #1

Located: 1320' FNL; 330' FWL, NW/4, Section 1-23S-17W,  
Pawnee County, Kansas

OWNER: Labsack Oil Production, Inc.  
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: November 19, 1981  
COMPLETED: November 26, 1981

TOTAL DEPTH: 4260'

<u>LOG</u>	<u>CASING RECORD</u>
0 - 110 Sand	Ran 7 joints 8 5/8" casing. 254.53' pipe set at 257' K.D. Cemented with 200 sacks 60/40 Pozmix with 3% cc. Plug down at 7:15 PM, 11-19-81, by Howco.
110 - 1093 Shale	
1093 - 1110 Anhydrite	
1110 - 1399 Shale	
1399 - 4260 Lime and Shale	Plugged.

Deviation Surveys: 3/4° at 2090'  
1 1/4° at 4200'