


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

15-145-20751-0001

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County. Sec. 1 Twp. 23 Rge. 17 E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
C E/2 E/2 NW
Lease Owner Midwestern Supply Co., Inc.
Lease Name White #1 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 11/9/76 _____ 19____
Plugging completed 11/18/76 _____ 19____
Reason for abandonment of well or producing formation
depleted. _____
If a producing well is abandoned, date of last production
_____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4159
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8		none
				4 1/2"	4159	2299'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped 48 barrels water into long string, it pressured up to 2000 lbs., pressure wouldn't break down. Sanded to 4046' with 2 sacks cement. Shot pipe at 3326', mud came in, pumped mud out of long string. Shot pipe at 2786', 2498', 2498' mud came in. Pumped mud out of long string, shot pipe at 2296', came loose, mud came in, pulled 12 joints and pumped mud back out. Pulled balance of pipe, 57 joints total. Allied plugged well with 10 sacks gel, 3 sacks hulls, 15 sacks gel, released plug, 125 sacks cement, 4% gel.

PLUGGING COMPLETE.

STATE CORPORATION COMMISSION

NOV 20 1976

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

11-29-76
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of November, 19 76

Margaret Melcher
Notary Public.

My commission expires




KANSAS GEOLOGICAL SOCIETY
508 East Murdock
Wichita, Kansas

MAR 25 1972

15-145-20251-0001

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

1-23-17W
E/2 E/2 NW KANSAS
RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1972
CONSERVATION DIVISION
Wichita, Kansas



WELL LOG ----- BOWEN-LANTERMAN #1
Located: 1320' FML, 2310' FWL, NW/4, Section 1-23S-17W,
Pawnee County, Kansas

OWNER: Ralph Bowen
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: March 15, 1972
COMPLETED: March 23, 1972

TOTAL DEPTH: 4156'

LOG	CASING RECORD
0 - 60 Sand and Clay	Ran 6 joints 8 5/8" 20#, 8rd, Rge. 3 new casing. 244.28' set at 256' K.B. with 250 sacks 60/110 Pozmix with HA 5. Plug down at 2:00 AM, 3-16-72.
60 - 1135 Shale	
1135 - 1480 Shale and Red Bed	
1480 - 1987 Shale and Shells	
1987 - 3702 Lime and Shale	
3702 - 4094 Lime	
4094 - 4136 Lime and Shale	
4136 - 4156 Lime and Chert	Flugged.

SAMPLE TOPS

SC	1097
HEEB	3604
TOR	3619
BN LM	3701
LANS	3711
CHTY CONG	4118
RTD	4156

"OWWO"
Pan Western Pet., Inc. #1 White
Card Issued 5/27/76
IP: D&A/Cong 4/17/76
NEW INFO: Re-entered 3/20/76 (See Completion Card)

STATE RECEIVED
DEC 13 1976
CONSERVATION DIVISION
Wichita, Kansas