

15-145-20251-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County. Sec. 1 Twp. 23S Rge. 17W (Box) (W)
Location as "NE/CNW/SW" or footage from lines 1320' FNL, 2310' FNL, NW/4
Lease Owner Ralph Bowen
Lease Name Bowen-Lanterman #1 Well No. 1
Office Address 4103 Panorama Drive, Hutchinson, Kansas 67501
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 23, 1972 19
Application for plugging filed March 23, 1972 19
Application for plugging approved March 23, 1972 19
Plugging commenced 9:00 PM, March 23, 1972 19
Plugging completed 12:00 PM, March 23, 1972 19
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4156' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	256'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud.
120 sacks Com. Pozmix - squeezed by
putting the swedge on the surface pipe -
pumping 120 sacks Pozmix down into
bottom of surface - by Halliburton

RECEIVED
STATE CORPORATION COMMISSION
JUN 30 1972
CONSERVATION DIVISION
Wichita, Kansas

6-30-72

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor STERLING DRILLING COMPANY
Address P. O. Box 129, Sterling, Kansas 67579

STATE OF KANSAS, COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) F. A. Wuellner
F. A. Wuellner, Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of June, 1972.
Bernard Lauder milk
Bernard Lauder milk, Notary Public.

My commission expires
BERNARD LAUDERMILK - NOTARY PUBLIC
My Commission Expires Jan. 22, 1974

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

15-145-20251-0000

WELL LOG ----- BOWEN-LANTERMAN #1
Located: 1320' FNL, 2310' FNL, NW/4, Section 1-23S-17W,
Pawnee County, Kansas

OWNER: Ralph Bowen
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: March 15, 1972
COMPLETED: March 23, 1972

TOTAL DEPTH: 4156'

<u>LOG</u>	
0 - 60	Sand and Clay
60 - 1135	Shale
1135 - 1480	Shale and Red Bed
1480 - 1987	Shale and Shells
1987 - 3702	Lime and Shale
3702 - 4094	Lime
4094 - 4136	Lime and Shale
4136 - 4156	Lime and Chert

CASING RECORD
Ran 6 joints 8 5/8" 20#, 8rd, Rge. 3 new casing. 244.28' set at 256' K.B. with 250 sacks 60/40 Pozmix with HA 5. Plug down at 2:00 AM, 3-16-72.

Plugged.

RECEIVED
STATE CORPORATION COMMISSION
JUN 30 1972
CONSERVATION DIVISION
Wichita, Kansas