


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

PAWNEE County. Sec. 1 Twp. 23 Rge. 17W (E) (W)
Location as "NE/CNW/SW" or footage from lines NW NW NW
Lease Owner HILTON DRILLING COMPANY, INC.
Lease Name LANTERMAN "B" Well No. 1
Office Address 925 PATTON ROAD, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) OIL WELL
Date well completed DECEMBER 27 19 54
Application for plugging filed JUNE 23 19 59
Application for plugging approved JUNE 26 19 59
Plugging commenced JULY 8 19 59
Plugging completed JULY 11 19 59
Reason for abandonment of well or producing formation DRY

If a producing well is abandoned, date of last production JULY 19 58
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well FRANK BROADFOOT - ST. JOHN, KANSAS
Producing formation CONGLOMERATE Depth to top 4141 Bottom 4230 Total Depth of Well 4258 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	222	NONE
				5-1/2"	4256	3500

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGED BACK WITH SAND FROM 4185' TO 4125'.
MIXED AND DUMPED 5 SACKS CEMENT FROM 4125' TO 4085'.
PULLED 5-1/2" CASING (3500'). MIXED AND PUMPED
IN 30 SACKS GEL MUD. PUMPED IN 100 SACKS CEMENT
FROM 300' TO BASE CELLAR.

RECEIVED
STATE CORPORATION COMMISSION
JUL 23 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor ACE PIPE PULLING COMPANY
Address BOX 304, GREATBEND, KANSAS

EM HILTON
STATE OF KANSAS, COUNTY OF BARTON, ss.
HARRY PEACOCK - LAND DEPARTMENT (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) [Signature]
GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 14TH day of JULY, 19 59
Carmen Reinhardt Leiker
CARMEN REINHARDT LEIKER Notary Public.

My commission expires JANUARY 26, 1963

PLUGGING
FILE SEC. 1 Twp. 23 R. 17W
BOOK PAGE 42 LINE 2

COPY

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
502 East Murdock, Wichita, Kansas

15-145-00378-0000


Company- HILTON DRILLING CO.
Farm- Lanterman "B" No. 1

SEC. 1 T. 23 R. 17W
NW NW NW

Total Depth. 4258'
Comm. 12-12-54 Comp. 12-27-54
Shot or Treated.
Contractor
Issued. 7-28-56

County Pawnee

KANSAS



CASING:
8 5/8" 222' com w/200 sx
5 1/2" 4256' com w/150 sx

Elevation. 2065' DE

Production. 30 BO

Figures indicate bottom of formations

sand	60
sand, lime	135
shale, shells	440
shale, red rock	560
sand, shale	700
red rock, shale, shells	1060
anhydrite	1087
shale, shells, salt	1595
shale, lime, shells	1965
shale, lime	3748
lime	3465
shale, lime	3500
lime	3602
lime, shale	3720
lime	4029
shale, lime	4185
lime, shale, chert	4213
chert, lime	4258
Total Depth	

Tops: Scout	
Heebner	3600
Brown Lime	3710
Lansing	3718
Conglomerate	4141
Viola	4230