

15-097-20662-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Kiowa SEC. 10 TWP. 28 S RGE. 16 E/W  
Location as in quarters or footage from lines:  
330 ENL 1650 FEL


Locate Well  
correctly on above  
Section Platt.

Lease Owner Texas Oil and Gas Corporation  
Lease Name Kendall Well No. A-3  
Office Address Suite 300 - 200 W. Douglas - Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): Gas  
Date Well Completed 8-27-80  
Application for plugging filed 10-29-82  
Plugging commenced 12-23-82  
Plugging completed 1-5-83 - 1:30 p. m.  
Reason for abandonment of well or producing formation Dry

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Duvant/Paul Luthi  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4,800  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	413	None
				4 1/2	4799	2730

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Plugged back at 4,670.  
Sand from 4,670 to 4,610  
4 sacks cment dumped with dump bailer. From 4,610 to 4,590.  
2 hulls - 15 jell - 70 sacks cement - 10 sacks jell  
1 sack hulls - Dropped plug - 150 sacks cement  
50-50 POZ - 2% jell - 3% C. C. - 1:30 - MAX 300 Shut in 100  
Allied Cement Co.  
Randy Zimmerman on location.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Clarke Corporation

STATE OF Kansas COUNTY OF Barber, ss.  
Elmo R. Morgenstern (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Elmo R. Morgenstern  
Medicine Lodge, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of Jan., 1983

My Commission expires: April 4, 1986.

Jessie Hamilton  
Notary Public.

JAN 10 1983

CONSERVATION DIVISION  
Wichita, Kansas

# KANSAS DRILLERS LOG

COMPANY Texas Oil & Gas Corp.

SEC. 10 T. 28S. 16W  
LOC. 330' FNL & 1650' FEL

FARM Kendall "A" NO. 3

COUNTY Kiowa

ROTARY TOTAL DEPTH 4,800'

COMM. July 31, 1980

COMP. August 8, 1980

CONTRACTOR H-30, Inc. (Rig #5)

ISSUED August 18, 1980

## CASING

10 3/4"

8 5/8" Set at 413' cemented w/400 sxs cement

5 1/2"

4 1/2" Set at 4,799' cemented w/125 sxs cement

ELEVATION 2,136' K.B.

FIGURES INDICATE BOTTOM OF FORMATIONS

Red Bed and Sand	425'
Red Bed and Shale	1,283'
Shale and Lime	2,140'
Red Bed and Shale	2,360'
Lime and Shale	2,650'
Shale and Lime	2,900'
Lime and Shale	3,390'
Shale and Lime	3,600'
Lime and Shale	4,478'
Shale and Lime	4,579'
Lime and Shale	4,772'
Shale and Lime	4,800'
Rotary Total Depth	4,800'

I hereby certify the above and foregoing to be  
a true and correct log of the above described  
well as shown by the drilling reports.

H-30, INC.

Dean Britting  
Dean Britting

State of Kansas )  
County of Sedgwick ) ss:

Subscribed and Sworn to before me a Notary Public  
in and for said county and state this 18th day of  
August, 1980.

Elsie Willison  
Elsie Willison - Notary Public

My Commission Expires:

July 25, 1982

RECEIVED  
STATE CORPORATION COMMISSION

OCT 28 1982

CONSERVATION DIVISION  
Wichita, Kansas