

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD


OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Rice County. Sec. 6 Twp. 21 Rge. (E) 7 (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines NEC NE 1/2 (NL NE) ?
Lease Owner Darby Petroleum Corporation
Lease Name Oden "A" Well No. 2
Office Address 1015 Philtower, Tulsa, Okla.
Character of Well (Completed as Oil, Gas or Dry Hole) Oil
Date, well completed ~~XXXXXXXXXXXX~~ September 16, 1939. 193
Application for plugging filed July 29, 1942. 193
Application for plugging approved July 31, 1942. 193
Plugging Commenced October 1, 1942. 193
Plugging Completed October 11, 1942. 193
Reason for abandonment of well or producing formation Ceased producing.

If a producing well is abandoned, date of last production June, 1941. 193
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Durkee, McPherson,
Producing formation Conglomerate Depth to top 3328 Bottom 3340 1/2 Total Depth of Well 3340 1/2 Feet.
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Conglomerate	Oil	3328	3340 1/2	8"	98'	None
				5"	3320'	2531' 8"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud 3345-20, cement (6 sacks) 3320-3290, Mud 3290-150, cement (10 sacks) 150-120, Mud 120-8', cement 8' to base of cellar (6 sacks)

PLUGGING
FILE SEC. 6-T-21-R-24
BOOK PAGE 46 LINE 38

Log on back

10-21-42

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Darby Petroleum Corporation
Address 1015 Philtower Bldg.,
Tulsa, Oklahoma.

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
W. H. Barclay (employee of owner) or owner or operator of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) W. H. Barclay
1015 Philtower, Tulsa, Oklahoma.
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of October, 1942.

My commission expires March 1, 1946. J. E. Waibel Notary Public.

FORMATION RECORD

	<u>FROM</u>	<u>TO</u>
Red bed, shale & shells	0	290
Shale & shells	290	565
Shale & salt	565	850
Shale	850	1000
Shale & lime	1000	1395
Shale	1395	1500
Shale & lime	1500	2135
Shale	2135	2355
Shale & lime	2355	2505
Lime	2505	2595
Lime & shale	2595	2670
Lime	2670	3280
Shale	3280	3325
Shale variegated	3325	3328
Conglomerate	3328	3330
S. L. M.	3330	3320
Conglomerate	3320	3340 $\frac{1}{2}$ T.D.