


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rice County, Sec. 6 Twp. 21 Rge. 7 ~~XX~~ (W)
Location as "NE/CNW/SW" or footage from lines C NW/4 SE/4
Lease Owner H. C. Bennett & C. E. Gould
Lease Name Hughes Well No. 1 A
Office Address 1212 Union National Bldg., Wichita, Kansas 67200
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 3/19 1972
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 19
Plugging completed 3/19/72 1972
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand		0	75	8 5/8"	75'	None
Shale		75	230	8 5/8"	155'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with mud to 225 ft. Set Plug & put in 25 sacks cement. Filled with 40 ft. and 10 sacks cement. 2 sacks in rathole. Plugging completed at 2:00 p. M., March 19, 1972 by State Plugger, Gilbert Toman, Holyrood, Kansas.


RECEIVED
STATE CORPORATION COMMISSION
MAR 28 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Blackstone Drilling, Inc.
Address Box 455, McPherson, Kansas 67460

STATE OF Kansas, COUNTY OF Sedgwick, ss.
H. C. Bennett & C. E. Gould (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. H. C. Bennett & C. E. Gould

(Signature) by: HCB Bennett
1212 Union National Bldg., Wichita, Kansas
(Address)



Subscribed and sworn to before me this 22nd day of March, 1972
Carroll A. Fisher
Notary Public.



Blackstone Drilling, Inc.

Box 455 • 523 West Kansas • Phone CH 1-1250

McPHERSON, KANSAS 67460

March 20, 1972

COMPANY: H. C. BENNETT & C. E. GOULD
 CONTRACTOR: BLACKSTONE DRILLING, INC.
 FARM: HUGHES 1A
 LOCATION: C NW/4 SE/4, Sec. 6-21S-7W,
 Rice County, Kansas
 COMMENCED: March 13, 1972
 COMPLETED: March 19, 1972
 ELEVATION: 1631 K. B.

0	to	75	Sand
75	to	1000	Shale
1000	to	1400	Shale & Lime
1400	to	1565	Lime
1565	to	2290	Shale & Lime
2290	to	2540	Lime & Shale
2540	to	2710	Lime
2710	to	2930	Shale & Lime
2930	to	3170	Lime
3170	to	3362	Lime & Shale
3362	to	3370	Lime
3370	to	3380	Mississippi
		3380	T. D.

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 28 1972
 CONSERVATION DIVISION
 Wichita, Kansas

Cut 12 1/4 inch hole to 230 ft. and run 232 ft. of 8 5/8 inch pipe, cemented with 230 sacks of cement at 230 ft., plug down at 2:45 P. M., March 14, 1972. Cut 7 7/8 inch hole to 3380 ft. Hole dry and abandoned. Filled with mud to 225 ft. Set plug and put in 25 sacks of cement. Filled to 40 ft. and 10 sacks of cement. 2 sacks in rathole. Plugging completed at 2:00 P. M., March 19, 1972. Plugging completed by Gilbert Toman, State Plugger, Holyrood, Kansas.

TOPS: BROWN LIME - 2875' LANSING - 2893' CONGLOMERATE - 3339' MISSISSIPPI - 3370

Measurements taken from K. B.

CERTIFICATE

I, H. J. Plouffe, President of Blackstone Drilling, Inc. do hereby certify that the above and foregoing is a true and correct copy fo log on your HUGHES 1A, located on the C NW/4 SE/4, Sec. 6-21S-7W, Rice County, Kansas as reflected by the files of Blackstone Drilling, Inc.

H. J. Plouffe
 H. J. Plouffe, President

Subscribed and sworn to before me a Notary Public in and for McPherson County, Kansas this 21st day of March, 1972.

Johnnie L. Schmidt
 Johnnie L. Schmidt - Notary Public

