

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Rice County. Sec. 6 Twp. 21 Rge. 7 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE SW SE

Lease Owner: West Supply Co., Inc.

Lease Name: Hughes #1 Well No.

Office Address: Chase, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 11-18-58 19

Plugging completed 11-26-58 19

Reason for abandonment of well or producing formation depletion

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well 3328 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				15-1/2"	132'	none
				7"	3326'	2963'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked the hole to 3328' and found it open. Filled w/sand to 3315' and dumped 5 sacks of cement with bailer. Pulled 7" casing. Cleared hole and set plug at 175', put in a 10' rock bridge and dumped 10 sacks of cement with bailer. Left set overnight, bailed hole dry and ran 40 more sacks of cement. Mudded the hole to 20', set rock bridge and ran 15 sacks of cement to base of cellar.

PLUGGING COMPLETED

RECEIVED  
STATE CORP  
DEC 1  
CONSERVATION DIVISION  
Wichita, Kansas  
12-1-58

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor West Supply Co., Inc.  
Address Chase, Kansas

STATE OF KANSAS COUNTY OF RICE  
I, Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Noel J. Knight*  
Chase, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 28th day of November, 19 58

9-27-62 *Thomas V. Diggins* Notary Public.

My commission expires

PLUGGING  
FILE SEC. 6 T. 21 R. 7W  
BOOK PAGE 130 LINE 5

15.159.06613.0000

Pr

Cromwell & Lewis

No.1 Hughes

6-21-7 W  
Rice County, Kansas

SEC SW SE

Commenced March 1, 1937

Casing:

15 1/2" 132' cemented with 150 sacks  
7" 3326 cemented with 100 sacks

sand and clay	65	
red rock and shale	85	
shale & lime	132	
sand and shale	350	
red rock & shells	410	
shale & shells	665	
salt & shells	890	
shale & shells	1155	
lime	1180	
shale & <del>sh</del> lime	1305	
broken lime	1422	
lime	1487	
shale & shells	1505	
lime	1545	
broken lime	1735	
shale & shells	2092	
shale & lime	2197	
shale & shells	2320	
lime	2350	
lime & shale	2415	
lime	2775	
shale	2783	
lime	2812	
broken lime	2885	
broken lime & shale	2895	
lime	2920	
lime soft; show oil	2928	
lime	3056	
broken lime	3111	
lime	3248	
lime & shale	3297	
3270	3273	S.L.M.
shale	3327	
conglomerate	3328	

very slight show oil-3327  
3326 derrick floor

Rotary completed March 17, 1937:

*Perforated  
to 924-32  
Rotary mud came in  
hole at this point  
when Perfo*

RECEIVED  
STATE CORPORATION COMMISSION

OCT 22 1958

DIVISION

PLUGGING  
FILE SEC 6 T 21 R 7W  
BOOK PAGE 130 LINE 5