

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION

FORM CP-1
 Rev. 03/92

RECEIVED
AUG 21 2003
KCC WICHITA

130 S. Market, Room 2078
 Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM
 (PLEASE TYPE FORM and File ONE Copy)

API #: 15-185-23193-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spu or completion date

WELL OPERATOR: Mull Drilling Co., Inc. (owner/company name) KCC LICENSE # 5144 (operator's)

ADDRESS: P.O. Box 2758 CITY: Wichita
 STATE: Kansas ZIP CODE: 67201-2758 CONTACT PHONE: 316-264-6366

LEASE: Andress Trust WELL#: 1-2 Section 2 Township 21s Range 13w
 140' S of S/2 Nw Ne SPOT LOCATION/QQQQ COUNTY: Stafford
800 FEET (in exact footage) FROM North LINE OF SECTION (NOT Lease Line)
1980 FEET (in exact footage) FROM East LINE OF SECTION (NOT Lease Line)

Check One: Oil Well _____ Gas Well _____ D&A XX SWD/ENHR WELL _____ Docket # _____
 CONDUCTOR CASING SIZE None SET AT NA CEMENTED WITH NA SACKS _____
 SURFACE CASING SIZE 8-5/8" SET AT 282' KB CEMENTED WITH 250 SACKS _____
 PRODUCTION CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS _____

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:
 ELEVATION 1862.7 G.L. 1871.7 K.B. T.D. 3680 PBDT _____ Anhydrite Depth 697'-722'
 (Stone Corral Formation)
 CONDITION OF WELL: GOOD XX POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING:
Received plugging orders 08/14/03 from Steve Middleton. Plugged using total of 155 sx of 60/40 Poz, 6% Gel & 1/4#/sx Celloflake. Heavy mud in hole and between all plugs. Bottom plug @ 3515' with 30sx. 2nd plug at 730' with 50sx. 3rd plug at 310' with 50sx. Top plug at 40' with 10 sx cemented to surface. Plugged rathole with 10sx, no mousehole. Plug down at 6:00 am, 08/15/03. Allied ticket # 15971. Reported to KCC 08/15/03.
 IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS ACO-1 FILED? ? (YES,NO)
 If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:
 Name: Gary Pugh/Gary Talbott Phone#: (316) 672-9508
 Address: P.O. Box 1006 City: Pratt State: Kansas
 PLUGGING CONTRACTOR: Sterling Drilling Company KCC LICENSE #: 5142
 (company name) (contractor's)
 Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 6:00 am on August 15, 2003.
 PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent _____

DATE: 08/15/03 AUTHORIZED OPERATOR OR AGENT: Gary M. Talbott
 (signature) Gary M. Talbott, Agent for Operator

DIST #1

6/10/04

6/10/04