

WELL PLUGGING RECORD

Give All Information Completely
• Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barton County. Sec. 24 Twp. 16 Rge. 12 (E/W) (W)

Location as "NE/CNW/SW" or footage from lines CE/2 NW SW

Lease Owner Great Bend Pipe & Supply Co.

Lease Name Dolecheck Well No. #3

Office Address West 10th-Box 414, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) _____

Date well completed _____ 19____

Application for plugging filed Yes 19____

Application for plugging approved Yes 19____


Plugging commenced 12-15 1957

Plugging completed 12-29 1957

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. R.M. Brundedge

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3336' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"		2,635'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Measured into T.D. 3336'.
Plugging started 12-15-57. Finished 12-29-57.
Plugged off bottom with sand to 3315' and dumped 5 sacks cement.
Shot 5 1/2" casing at 2,635'. Plugged well as follows: Mud to 275'. Set rock bridge and dumped 25 sacks cement. Filled hole with mud to 40'. Set rock bridge and mixed 10 sacks cement for cap on well. Well completed.

RECEIVED
STATE CORPORATION COMMISSION

JAN 3 1958

CONSERVATION DIVISION
WICHITA, KANSAS

1-3-58

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J.O. Forbes d/b/a Forbes Casing Pulling Co.

Address Box 221, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss. J.O. Forbes

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.O. Forbes
Box 221, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 31st day of December, 1957

My commission expires November 8, 1960

F. Betty S. Edman
Notary Public.

PLUGGING
FILE - SEC 24 T. 16 R. 12 W
BOOK PAGE 64 LINE 10

15-009-03358-00-00
 KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS


COMPANY **BLACK-MARSHALL OIL CO.**

SEC. **24** **16** **12W**
 LOC. **ONE** **SW** **SW** **R.**

FARM **Dolechek Estate** NO. **3**

TOTAL DEPTH **3331' RTD** **CHT. 3336'**
 COMM. **7-2-44** COMP. **7-13-44**
 SHOT OR TREATED
 CONTRACTOR **Ferrell-Young Drlg. Co.**
 ISSUED **9-9-44**

COUNTY **Barber**



CASING

20	10	
15	B	5/8 236' w/85 sx cem.
12	S	6 1/2 3328' 2/125 sx cem.
13	S	

ELEVATION **1909'**

PRODUCTION **441 bbls.**

FIGURES INDICATE BOTTOM OF FORMATIONS

cellar	4
shale-shells	175
sand	202
sand-shells	230
lime	236
shale-shells	255
shale	500
Iron -shale	520
shale-shells	780
anhydrite	805
shale-shells	1190
salt	1375
shale-shells	1520
lime-shale blk	2075
shale-shells	2650
lime	3010
shale-shells	3076
lime	3328
sand	3331

Total Depth Rotary

TOPS: Sample R.T.M.
 Lansing 3076
 Gorham sand 3028
 Cable Tool T.D. 3336'

RECEIVED
 U.S. GEOLOGICAL SURVEY COMMISSION
 NOV 30 1957
 GEOLOGICAL DIVISION

PLUGGING
 FILE NO. **24 T. 16 R. 12 W**
 BOOK PAGE **64** LINE **10**