

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-009-03361-00-00
 API NUMBER.

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE NAME Dolacheck

WELL NUMBER #7

_____ Ft. from S Section Line

_____ Ft. from E Section Line

SEC. 24 TWP. 16 RGE. 12 (E) or (W)

COUNTY Barton

LEASE OPERATOR N.C.R.A.

ADDRESS Box 6
Great Bend, KS 67530

PHONE # (316) 793-7824 OPERATORS LICENSE NO. 5565

Date Well Completed _____

Character of Well _____

Plugging Commenced 8/18/88

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8/26/88

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #6 Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3340

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	282	none
				5 1/2	3332	992

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged off bottom with sand to 3280', ran 5 sacks cement. Shot @2518', 2007', 1530', 1210', 992'. Plugged surface with 200 sacks cement, 100# hulls, 60/40 pos, 6% gel 3%cc.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor KELSO CASING PULLING, INC. License No. 6050

Address P.O. Box 347 Chase, KS 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 14th day of September, 1988

Jane Hoover
 Notary Public

Commission Expires: _____

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 16 1988
 CONSERVATION DIVISION
 Wichita, Kansas
 9-16-88



15-009-03361-00-00

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


COPY

Company BLACK-MARSHALL OIL CO.
Farm Dolechok Est. No. 7

24 16
SEC. 24 T. 16 R. 12 W
S1 E2 S1

Total Depth. 3340'
Comm. 8-21-46 Comp. 9-7-46
Shot or Traced.
Contractor. Black-Marshall Oil Co.
Issued. 10-26-46

County Barton
KANSAS



Elevation. 1900

Production. 306 B.

CASING 282' 90 RT
8 5/8" 300' Cum.
5 1/2" 3332' Cum. 100 M
3332

Figures indicate Bottom of Formations.

clay & sand	234	235
shale & sand	282	282
shale	400	400
shale & red bed	558	554
shale	775	775
anhydrite	795	795
shale & shells	1180	1180
shale & salt	1480	1480
shale	1695	1695
shale & lime	1800	1800
lime	1990	1990
shale & lime	2166	
shale	2310	
shale & lime	2408	
shale & shells	2528	
shale	2675	
shale & shells	2755	
lime	2948	
shale & lime brks	3025	
shale	3060	
lime	3105	3105
shale & lime	3160	3160
lime	3320	
lime	3340	
Total Depth.		

K. G. S. LIBRARY

Tops:
anhydrite 775
ansing K. C. 3080
Sand 3331

SSO 3060-84'

RECEIVED
STATE CORPORATION COMMISSION

JUL 21 1988

CONSERVATION DIVISION
Wichita, Kansas