

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-009-03362-00-00  
API NUMBER \_\_\_\_\_

LEASE NAME Dolechek Estate

WELL NUMBER #8

SPOT LOCATION SW SE SW

SEC. 24 TWP. 16 RGE. 12 (E) or (W)

COUNTY Barton

Date Well Completed 2-8

Plugging Commenced 2-19-86

Plugging Completed 2-25-86

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR N.C.R.A.

ADDRESS P.O. Box 6 Great Bend, Kansas 67530

PHONE # (316) 793-7824 OPERATORS LICENSE NO. \_\_\_\_\_

Character of Well Inj.  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 3359

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	270'	none
				5-1/2"	3342'	1695'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.  
Plugged off bottom with sand to 3300' and ran 5 sacks cement. Shot casing @1695', and layed down 53 joints (1695') of 5-1/2" casing. Plugged surface with 5 sacks hulls, 200 sacks 60/40 pos, 6% gel.

Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050  
Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso

(employee of operator) or

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 26th day of February, 1986

HELEN L. HOOVER  
STATE CORPORATION COMMISSION Notary Public

My Commission expires:



FEB 28 1986

CONSERVATION DIVISION

Form CP-4  
Revised 01-84

15-009-03362-00-00

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY  
412 Union National Bk. Bldg., Wichita, Kansas

**COPY**


12 W

Company - BLACK-MARSHALL OIL CO.  
Farm - Golechok Estate No. 8

SEC. 24 T. 18 R. 18 W  
SW SE SW

Total Depth. 3359'  
Comm. 9-11-46 Comp. 9-20-46  
Shot or Treated.  
Contractor. Black-Marshall Oil Co.  
Issued. 11-23-46

County. Barton  
KANSAS



Elevation. 1906'

Production. Phy. Pot. 600 B.

CASING

8 5/8" 267' Com. 90 M  
5 1/2" 3342' Com. 100 M  
3342'

Figures indicate Bottom of Formations.

clay & sand	285
shale & shells	287
shale & red bed	395
sand	455
shale " shells	620
shale	775
anhydrite	803
red bed & shale	1020
shale	1180
salt	1365
shale " shells	1490
shale & lime	1850
lime	1910
shale " lime	2040
shale	2220
shale " shells	2370
shale	2520
shale " lime	3195
lime	3348
Rotary T. D.	
lime	3359
Total Depth (Cable)	

Tops:	
Anhydrite	775
Lensing (no shows)	3084
Sand	3341

**K. G. S. LIBRARY**

RECEIVED  
STATE CORPORATION COMMISSION

NOV 9 1946

CONSERVATION DIVISION  
Wichita, Kansas