


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County. Sec. 24 Twp. 16 Rge. 12 (E) (W)
Location as "NE/CNW/WSW" or footage from lines SE SW SE
Lease Owner National Cooperative Refinery Association
Lease Name Paul Dolechek Well No. 8
Office Address _____
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed January 5, 19 47
Application for plugging filed July 1, 19 55
Application for plugging approved July 5, 19 55
Plugging commenced July 12, 19 55
Plugging completed July 15, 19 55
Reason for abandonment of well or producing formation Depletion

If a producing well is abandoned, date of last production June 10, 19 55
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Warren Horner
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3120 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	275'	None
				5 1/2"	3338'	2742'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole was plugged back from 3348 to 3120 and casing perforated from 3088 to 3091 in a recent workover.

Filled the hole with sand from 3120' to 3075' and ran 5 sacks of cement. Cement filled to 3035'. Mudded the hole to 275', set a 10' rock bridge and ran 20 sacks of cement. Mudded the hole to 40', set a 10' rock bridge and ran 10 sacks of cement on top.

15-009-03375-00-00
STATE CORPORATION COMMISSION
STATE CORP.
JUL 2 1955
CONSERVATION DIVISION
WICHITA, KANSAS

7-22-55

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor West Supply Company, Inc.
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
C. R. Sears (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. R. Sears
305 Rule Bldg., Wichita, Kansas C. R. Sears
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of July, 19 55

My commission expires June 30, 1958

C. Orville May
C. Orville May Notary Public

PLUGGING
FILED SEC 24 T 16 R 12 W
BOOK PAGE 131 LINE 20

COMPANY: Black-Marshall Oil Company
CONTRACTOR: Black-Marshall Oil Company

FARM: P. Dolechek #8
LOCATION: SE SW SE 24-16-12
Barton Co., Kansas

COMMENCED: 12-16-46
COMPLETED: 12-28-46

CASING RECORD:

ELEVATION: 1913'
PRODUCTION:

8 5/8" @ 275' - 90 sks.
5 1/2" @ 3338' - 100 sks.

<u>Formation</u>	<u>Depth</u>
Surface clay and shale	45
Clay and sand	240
Shale and shells	275
Shale and sand	475
Shale, shells and red bed	775
Anhydrite	795
Shale and red bed	1345
Salt and shale	1440
Shale and shells	1575
Shale and lime	1930
Lime	1990
Shale and lime	2175
Shale and shells	2605
Shale and lime	2780
Broken lime	2845
Lime	2890
Shale and lime	3190
Lime	3339
ROTARY TOTAL DEPTH	3339

<u>Tops</u>	
Anhydrite	- 775'
Lansing K.C.	- 3086'
Gorham Sand	- 3336'

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

We hereby certify this to be a correct and accurate log of the above described well as shown by the daily drilling reports.

BLACK-MARSHALL OIL COMPANY

[Signature]
Vice-President

Subscribed and sworn to before me this 2nd day of January, 1947.

[Signature]
Notary Public

My commission expires February 19, 1949.

PLUGGING
FILE SEC 24 T 16 R (2W)
BOOK PAGE 131 LINE 20

RECEIVED
STATE CORPORATE COMMISSION
JUL 5 - 1955
CONSERVATION DIVISION
Wichita, Kansas