


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

## WELL PLUGGING RECORD

NORTH

Locate well correctly on above  
Section Plat

Location as "NE/CNW/SW" or footage from lines. Barton County. Sec. 24 Twp. 16 Rge. 12 (E) W (W)  
Lease Owner Spector Pipe and Supply Inc.  
Lease Name P. Dolechek Well No. 9  
Office Address Russell, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) oil  
Date well completed 1-31-47 19  
Application for plugging filed March 6, 1966 19  
Application for plugging approved March 7, 1966 19  
Plugging commenced March 26, 1966 19  
Plugging completed April 1, 1966 19  
Reason for abandonment of well or producing formation failure to produce profitably  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan, Holyrod, Kansas  
Producing formation Arbuckle Depth to top 3349 Bottom 3359 Total Depth of Well 3362 Feet  
Show depth and thickness of all water, oil and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	276 ft.	none
				5 1/2	3359 ft.	2642 feet

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged back to 3140 feet, dumped 5 sacks cement.  
Set a Rack Bridge at 270 feet, dumped 25 sacks  
cement and put 10 sacks on top.

RECEIVED  
STATE CORPORATION COMMISSION

APR 8 1966

4-8-66

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Lynch Casing Pulling Company  
Address R. RT. 4 Great Bend, Kansas No. 457

STATE OF Kansas, COUNTY OF Russell, ss.

Spector Pipe & Supply, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Morton Spector(Address) Russell, KansasSUBSCRIBED AND SWORN TO before me this 5th day of April, 1966My commission expires March 9, 1970

Notary Public.

## WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY

412 Union National Bk. Bldg., Wichita, Kansas

15-009-03376-00-00

COPY

Company - BLACK-MARSHALL OIL COMPANY  
Farm - P. Polochok No. 9SEC. 24 T. 16 S. 12W  
SW NE SE

Total Depth. 3362'

Comm. 1-22-47

Comp. 1-31-47


Shot or Treated.

Contractor. Black-Marshall Oil Co.

Issued. 4-12-47

County. Barton

KANSAS



## CASINGS

8-5/8" 276' Com. w/ 90 sx  
5-1/2" 335' Com. w/100 sx

Elevation. \_\_\_\_\_

Production. 300 bbls. oil & 6%  
wtr

Figures Indicate Bottom of Formations.

cellar	4
post rock & clay	100
sand & shale	276
shale, shells & sand	685
shale & red bed	770
anhydrite	795
shale & shells	1190
salt	1235
salt, shale & shells	1490
shale & lime	1845
lime bro.	1930
shale & lime	2200
shale & shells	2385
shale & lime	2890
lime bro.	2975
shale & lime	3130
lime	3175
shale & lime	3250
lime	3314
bro. lime (R.T.D.)	3351
sand	3352
sand-very lt S.O.	3354
sand granite wash	3356
48.73 bbls per hr, 300	
ft. off bottom	
sand	3358
sand granite wash	3360
sand Quartz	3362
F.U. 1000' in 1 hr	
1600' in 1 hr. 40 min.	
at 3362'	
Total Depth	3362

## Tops:

Anhydrite	770
Kansas City	3074
Sand	3349

RECEIVED  
STATE CORPORATION COMMISSION

MAR 7 1966

CONSERVATION DIVISION  
Wichita, Kansas