


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
300 Blitting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plugging
off formations.

Barton County. Sec. 25 Twp. 16 Rge. (E) 12 (W) 12
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. CWL NW NE
Lease Owner Natl. Coop. Ref. Assoc. Prod. Dept. Div. B
Lease Name P. Dolechek Well No. 10
Office Address Box 6, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 2, 1947
Application for plugging filed September 3 1947
Application for plugging approved September 4 1947
Plugging commenced September 16, 1947
Plugging completed September 25, 1947
Reason for abandonment of well or producing formation.....
If a producing well is abandoned, date of last production..... 19.....
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. H. W. Kerr
Producing formation Regan sand Depth to top 3343' Bottom 3346' Total Depth of Well 3446' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5 $\frac{1}{2}$ " Csg.	3324'	3020' 7"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Filled bottom of hole to 3330' with heavy mud,
run 5 sacks cement. Filled hole with heavy mud
to 275', set wood plug and run 15 sacks cement.
Filled hole with heavy mud to 25', set wood plug,
run 10 sacks cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Natl. Coop. Ref. Assoc. Prod. Dept. Div. B
Address Box 6, Great Bend, Kansas


STATE OF Kansas, COUNTY OF Barton, ss.
Harry T. Black (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harry T. Black OCT 10 1947 10-10-47
Clifton, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 8 day of Feb. 1947

My commission expires Feb. 5, 1951

Notary Public.



15-009-03377-00-00

COMPANY: Black-Marshall Oil Company
CONTRACTOR: Black-Marshall Oil Company

FARM: P. Dolechek # 10
LOCATION: CWL NW NE 24-16-12W
Barton County, Kansas

COMMENCED: 2-13-47
COMPLETED: 2-23-47

GASING RECORD:
8 5/8" @ 520' - 175 sks
5 1/2" @ 3324' 100 sks

ELEVATION: 1882'
PRODUCTION:

<u>Formation</u>	<u>Depth</u>
Post rock, sand and shale	170
Shale and shells	410
Shale	450
Sand	465
Shale, shells and sand	517
Red Rock	700
Red bed	755
Anhydrite	785
Shale and shells	1185
Salt	1400
Shale and shells	1450
Shale and lime	1850
Bro. lime	1930
Shale and lime	2200
Shale	2340
Shale and lime	2800
Lime	2915
Shale and lime	3030
Bro. lime	3115
Lime	3210
Bro. lime	3295
Lime	3325

	<u>TOPS</u>
Anhydrite	755'
Conglomerate	3315'
Gorham Sand	3324'

ROTARY TOTAL DEPTH 3325

STATE OF KANSAS)
) SS
COUNTY OF BARTON)

We hereby certify this to be a correct and accurate log of the above described well as shown by the daily drilling reports.

BLACK-MARSHALL OIL COMPANY

[Signature]
Vice-President

Subscribed and sworn to before me this 28th day of February, 1947.

[Signature]
Notary Public

My commission expires February 19, 1949.

PLUGGING
FILE SEC 24-16-12W
BOOK PAGE 130 1/7