

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-009-03378-00-00
API NUMBER

LEASE NAME Paul Dolecheck

WELL NUMBER #13

_____ Ft. from S Section Line

_____ Ft. from E Section Line

SEC. 24 TWP. 16 RGE. 12 (E) of (W)

COUNTY Barton

Date Well Completed _____

Plugging Commenced 8/25/88

Plugging Completed 9/7/88

LEASE OPERATOR N.C.R.A.

ADDRESS Box 6
Great Bend, KS 67530

PHONE # (316) 793-7824 OPERATORS LICENSE NO. 5565

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? _____ Dist. #6 Hays, Kansas

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3372

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORD | 9-12-88 CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	251'	none
				5 1/2"	3372'	2241.80'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Plugged off bottom with sand to 3290', ran 5 sacks cement. Shot pipe @2822', 2514', 2241', pulled a total of 70 joints of 5 1/2" casing. Pumped 500# hulls and 200 sacks 60/40 pos, 6% gel. Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) P.O. Box 347 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 8th day of September, 1988

Jane Hoover
Notary Public

My Commission Expires:



15-009-03378-00-00

COPY


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company: NATIONAL COOPERATIVE REFINERY ASS'N, SEC. 24 T. 16 R. 12W
Farm: Paul Dolechek No. 13 SW NW SE

Total Depth. 3372
Comm. 4-12-53 Comp. 4-27-53
Shot or Treated.
Contractor. John Lindas Oil Co., Inc.
Issued. 5-30-53

County Barton

KANSAS



Elevation. 1899 KB

Production. 292 BO, no water

CASING:

8 5/8 set at 280' w/ 130 sx cement
5 1/2 set at 3372' w/ 75 sx cement

Figures indicate Bottom of Formations.

post rock & shells	75
sand	95
shale	140
sand	155
shale & shells	570
red bed	770
anhydrite	800
shale & shells	1480
lime & shale	1510
lime	2065
lime & shale	2090
lime	2145
lime & shale	2695
lime	3332
coring	3372
Total Depth	

SCOUT TOPS:	
Anhydrite	770
Lansing	3071
Conglomerate	3326
Conglomerate sand	3329
Quartzite	3370

K. G. S. LIBRARY

RECEIVED
STATE CORPORATION COMMISSION

10 24 1988

CONSERVATION DIVISION
Wichita, Kansas