


5-145-01147-2001

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavits  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above  
Section Plat

Pawnee County. Sec. 3 Twp. 22 Rge. 17 (E) 17 (W)  
Location as "NE/CNW/SW" or footage from lines SE, NE SW  
Lease Owner Clark Knight Drg. Co. Inc  
Lease Name Hutchinson Well No. 7  
Office Address Box 969, Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed July 13 1962  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced July 27 1962  
Plugging completed August 12 1962  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. LaKamp  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4264 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4"	195'	none
				5 1/2"	4263'	2263'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Top Perforation 4156'

Sanded hole to 4140' - dumped 5 sks cement -  
pulled casing - pumped in 15 sks mud and  
75 sks cement through surface pipe.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 19 1962

CONSERVATION DIVISION  
Wichita, Kansas

10-19-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & D Casing Pulling Co. License #236  
Address Box 572, Hutchinson, Kansas

STATE OF Kansas COUNTY OF Barton, ss.

\_\_\_\_\_, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Clark Knight Drg. Co. Inc  
Box 969, Great Bend, Kansas. President  
(Address)

SUBSCRIBED AND SWORN TO before me this 18 day of October, 1962

My commission expires 8-11-65

Belle Myers  
Notary Public.



WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


15-145-01147-000(

Company- CLARK KNIGHT DRILLING & N.C.R.A.  
Farm- Hutchinson No. 7

SEC. 3 T. 23 R. 17W  
SE NE SW

Total Depth. 4264'  
Comm. 11-4-55 Comp. 11-19-55  
Shot or Treated.  
Contractor.  
Issued. 8-11-56

County Pawnee  
KANSAS



CASING:  
8 5/8" 187'  
5 1/2" 4263'

Elevation. 2071'

Production. 1142 BOPD

Figures indicate Bottom of Formations.

sand	40
shale, shells	187
shale	450
shale, shells & red rock	489
shale, shells	580
sand, shale	660
red rock, shale	775
shale, shells	1115
anhydrite	1150
shale; shells	2000
shale, lime	2368
lime	2450
lime, shells	3410
lime	3495
lime, shale	3849
lime	4120
lime, shale	4160
Conglomerate	4235
lime	4264
Total Depth	

Tops:	
Anhydrite	1115
Base Anhydrite	1150
Heebner	3609
Toronto	3626
Douglas	3641
Brown Lime	3716
Mansing-Kansas City	3722
Base Kansas City	4002
Pt Scott	4128
Cherokee Shale	4132
Conglomerate	4152
Mississippi	4214
Kinderhook	4244
Viola	4255
TD	4264

RECEIVED  
STATE CORPORATION COMMISSION  
OCT. 19 1962  
CONSERVATION DIVISION  
Wichita, Kansas