


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD 15-145-01145-0000

Pawnee County, Sec. 3 Twp. 23 Rge. 17 (E) 17 (W)

Location as "NE/CNW/SW" or footage from lines SE SW NW
Lease Owner Clark Knight
Lease Name Hutchinson Well No. 5
Office Address Box 969 Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed _____ 19____
Application for plugging filed 10-20 19 62
Application for plugging approved _____ 19____
Plugging commenced 10-22 19 62
Plugging completed 11-6 19 62
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp Jr.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4260 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4	186	none
				5 1/2	4259	3355'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Top Perforation 4150'

Sanded hole to 4140' - dumped 5 sks cement - pulled casing - pumped in 10 sks mud and 75 sks cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 1 1963

CONSERVATION DIVISION
Wichita, Kansas

3-1-63

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & D Casing Pulling Co License #236
Address Box 572, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.

J. W. Railsback

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. W. Railsback

Box 572, Hutchinson, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of November, 1962

Wilma A. Clark

Notary Public.

My commission expires Nov. 16, 1965



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-145-01145-0000

Company- L.C. KNIGHT & N.C.R.A.
Farm- Hutchinson No. 5

SEC. 3 T. 23 R.17W
SE SW NW

Total Depth. 4260'
Comm. 6-29-55 Comp. 7-14-55
Shot or Treated.
Contractor.
Issued. 8-4-56

County Pawnee
KANSAS



CASING:
10 3/4" 186' w/100 sx cem.
5 1/2" 4259'

Elevation. 2069

Production. 350 B.

Figures Indicate Bottom of Formations.

surface	186
shale shells	420
sand	455
shale	510
sand	635
shale shells	1093
Anhydrite	1115
shale-shells	1450
shale	1800
shale-shells	1900
shale-lime	2395
lime	2520
lime-shale	3225
lime	3285
lime-shale	3375
lime	4142
Conglomerate	4187
cherty lime	4224
lime	4260
Total Depth	

TOPS:	
Anhydrite	1093
B. Anhydrite	1115
Heebner	3601
Toronto	3618
Douglas	3632
Brwn lime	3708
Lansing Kansas City	3717
B/Kansas City	3992
Ft. Scott	4116
Cherokee shale	4123
Cherokee sand	4133
Conglomerate	4151
Mississippi	4200
Kinderhook	4242
Viola	4250

RECEIVED
STATE CORPORATION COMMISSION

MAR 1 1963

CONSERVATION DEPARTMENT
WICHITA, KANSAS