


Give All Information Completely
Make Required Affidavit
Mail or Deliver Reg. 1 to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD 15-145-61144-0000

Pawnee County. Sec. 3 Twp. 23 Rge. (E) 17 (W)

Location as "NE/CNW/SW" or footage from lines. NW SE SW
Lease Owner Clark Knight
Lease Name Hutchinson Well No. 4
Office Address Box 969, Great Bend Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 19
Application for plugging filed 10-20 19 62
Application for plugging approved 19
Plugging commenced 10-27 19 62
Plugging completed 11-6 19 62
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well W. L. LacKamp Jr.
Producing formation Depth to top Bottom Total Depth of Well 4270 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4	145	none
				5 1/2	4269	2696'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Top Perforation 4158'

Sanded hole to 4150' - dumped 5 sks cement - pulled casing - pumped in 10 sks mud and 75 sks cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 1 1963

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & D Casing Pulling Co. License #236
Address Box 572, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.
J. W. Railsback (employee of owner) or (owner or operator)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

J. W. Railsback
Box 572 Hutchinson, Kan
(Address)

SUBSCRIBED AND SWORN TO before me this 15 day of November, 19 62

Wilma A. Clark

Notary Public.

My commission expires Nov. 16, 1965



15-145-01144-8000

Drillers Log.

Company: Clark Knight Drg. Co; Inc.
Farm: Hutchinson #4

Sec. 3-T23-R117W, NW SE SW
Pawnee County, Kansas.

T.D/ 4270'
Comm. 4/25/55 Comp. 5/6/55

Casing:

8 5/8" 112' Cm. 80
5 1/2" 4269' " " 75

Bottom figures.

Surface	112
Shells	425
Shale, shells	450
Sand	460
Shells, shale	515
Sand	640
Shale, shells	1090
Anhy.	1100
Shells, shale	1455
Shale	1810
Shale, shells	1930
Shale, lime	2400
Lime	2530
Lime, shale	3290
Lime	3720
Sand	4150
Shale, lime	4160
Lime	4250
Shale	4260
Lime	4268
T.D.	

Form. Tops.

Elev.	2074
Anhy.	1100
Doug.	3669
Lans. KC	3721
Cher. sand.	4142
Cong.	4158
Miss. Lm.	4219
Viola	4262
T.D.	4270

RECEIVED
STATE CORPORATION COMMISSION

MAR 1 1963

CONSERVATION DIVISION
Wichita, Kansas