

WELL PLUGGING RECORD 15-145-01143-0000

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Pawnee County. Sec. 3 Twp. 23 Rge. 17 (E) (W)

NORTH

Locate well correctly on above
Section Plat

Location as "NE/CNW*SW*" or footage from lines NW NW SW
Lease Owner Clark Knight Drilling Inc.
Lease Name Hutghinson Well No. 3
Office Address 2133 Walnut Drive, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed _____ 19____
Application for plugging filed August 16 1962
Application for plugging approved August 24 19 62
Plugging commenced August 24 19 62
Plugging completed August 28 19 62
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. LaKamp, Stafford
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4254 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1208	
				5 1/2	4254	4254

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with sand to 430', dumped 5 sacks cement
Shot 2 hole @ 800'
Pumped 20 bbls oil and 66 bbls water
Shot pipe 3604', 3313', 3217', 3129', 2930'.
Mix 15 sacks mud and 75 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

OCT 30 1962

CONSERVATION DIVISION
Wichita, Kansas

10-30-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pipe Pullers, Inc.
Address Box 186, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Pipe Pullers, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]

(Address)

SUBSCRIBED AND SWORN TO before me this 12 day of September, 1962

My commission expires December 18, 1962 Juanita L. Meyer Notary Public.

HOWELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-145-01143-0000

Company- CLARK KNIGHT DRIG.
Farm- Hutchinson No. 3

SEC. 3 T. 23 R. 17W
NW NE SW

Total Depth. 4256'
Comm. 4-16-55 Comp. 4-22-55
Shot or Treated.
Contractor.
Issued. 7-28-56

County Pawnee
KANSAS



Elevation. 2063'

Production. 920 BO

CASINGS:

8 5/8" 208' cem w/125 sx
5 1/2" 4255' cem.

Figures indicate Bottom of Formations.

sand	30
sand, shale	208
shale, shells	415
sand	440
shale, shells	540
sand	630
shale, shells	1090
anhydrite	1115
shale, shells	1960
lime, shale	2240
lime	2370
lime, shale	3405
lime	3545
lime, shale	3729
lime	4135
Conglomerate	4256
Total Depth	

Tops	
Anhydrite	1090
Base Anhydrite	1115
Toronto	3611
Douglas	3624
Brown Lime	3703
Lansing	3711
Base Kansas City	3986
Cherokee Sand	4120
Conglomerate	4141
Mississippi	4200
Kinderhook	4230
Viola	4255

RECEIVED
STATE CORPORATION COMMISSION

OCT 30 1962

CONSERVATION DIVISION
Wichita, Kansas