

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD 15-145-01141-0060

Pawnee County, Sec. 3 Twp. 23 Rge. 17 (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW NW

Lease Owner Clark Knight Drilling Co.

Lease Name Hutchinson Well No. 1

Office Address 2133 Walnut Drive, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced September 5 1962

Plugging completed September 10 1962

Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Mr. Lackamp, Stafford

Producing formation Depth to top Bottom Total Depth of Well 4408 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	298	
				5 1/2	4276	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sand to 4000', rock bridge and dump 5 sacks cement
Shot pipe 3583', 3520', 3410', 3315'.
Well started flowing oil & water
Capped 15 sacks mud and 75 sacks cement

RECEIVED
STATE CORPORATION COMMISSION

OCT 30 1962

CONSERVATION DIVISION
Wichita, Kansas

10-30-62

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pipe Pullers, Inc.

Address Box 486, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

Pipe Pullers, Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *R. D. Myers*

(Address)

SUBSCRIBED AND SWORN TO before me this 12 day of September, 1962

My commission expires December 18, 1962

Granite R. Myers
Notary Public.



ME

15-145-61141-0000

Drillers Log.

Company: Clark Knight Drg. Co; Inc.

Sec. 3 T 23 R 17W

Farm Hutchinson #1.

NW NW NW

Total Depth. 4409'

County Pawnee Kansas.

Comm. 8-14-54 Comp. 8-31/54.

Elevation: 2061 RB

Casing: 8" 205'
5 1/2" 4276'

Prod. 1200 bbl. oil.

Figures indicate bottom of formation.

Sand.	60'
sand & shells	210
sand & shale	430
Shale & shells	525
Sand	628
Shale & shells	1082
Anhydrite	1090
Shale-shells	1960
Shale	2090
Lime, shale	2250
Lime	2350
Lime-shale	3490
Lime	3610
Lime, shale	3675
Lime	4115
Sand	4140
Chert	4162
Core -Chert	4175-93
Chert, shale	4249
Chert	4275
Sand	4372
Lime	4409
Total Depth	4409

Tops.

Cherokee sand	4131
Miss.	4141
Viola	4250
Simpson	4344
Arbuckle	4372.

RECEIVED
STATE CORPORATION COMMISSION

OCT 30 1962

CONSERVATION DIVISION
Wichita, Kansas