


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

15-145-00302-0000

NORTH



Locate well correctly on above
Section Plat

Pawnee County, Sec. 3 Twp. 23 Rge. 17 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines SW SW SE
Lease Owner Colorado Oil & Gas Corporation
Lease Name Hutchinson "H" Well No. 3
Office Address Box 1030, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 15 1955
Application for plugging filed December 4 1961
Application for plugging approved December 6 1961
Plugging commenced December 5 1961
Plugging completed December 8 1961
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production March 1 1957
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Lackamp
Producing formation Conglomerate Chert Depth to top 4184 Bottom _____ Total Depth of Well 4303 Feet
Show depth and thickness of all water, oil and gas formations. PBTD 4251

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	249'	None
				5-1/2"	4303'	3368'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 4250', ran 60 gal. of sand to 4200' and dumped 5 sacks of cement @ 4200' with dump bailer. Pulled 5-1/2" casing. Bailed heavy mud to 30' from 6', could not bail surface pipe down. Squeezed surface with 5 sacks of jell and 70 sacks of cement to 12' and capped with 5 sacks of cement.

PLUGGING COMPLETE.

STATE OF KANSAS
CONSERVATION DIVISION
Wichita, Kansas

12-29-61

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Bill K. Henrichs (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill K. Henrichs
P.O. Box 1030, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 28th day of December, 1961

Helen L. Martin
Helen L. Martin Notary Public.

My commission expires August 19, 1963

15-145 60302-0000

DRILLERS LOG

Hutchinson "H" Well No. 3

Loc: SW SW SE

Sec: 3-23-17

Pawnee County, Kansas

Contractor: Honaker Drig., Inc.

Comm: 2-8-55

Comp: 2-25-55

Elevation: 2098 D.F.

Total Rotary Depth: 4304'

Casing: 8-5/8" set @ 246'

5-1/2" set @ 4303'

0	40	Sand & Clay.	
40	100	Shale & Sand.	
100	600	Shale & Shells.	8-5/8" surface casing
600	775	Red Bed.	cemented @ 246' w/ 175
775	840	Shale & Shells.	sacks cement, 2 sacks
840	1130	Red Bed, Shale & Sand.	calcium chloride.
1130	1165	Anhydrite.	
1165	1940	Shale & Shells.	
1940	2110	Lime & Shale.	
2110	2235	Lime Broken.	
2235	2425	Lime & Shale.	
2425	2500	Lime.	
2500	3385	Shale & Lime.	
3385	3485	Lime & Shale.	
3485	3575	Lime.	
3575	3650	Lime & Shale.	
3650	3745	Shale & Lime.	
3745	4160	Lime.	
4160	4229	Conglomerate.	
4229	4241	Lime.	
4241	4300	Chert & Shale.	
4300	4304	Chert & Lime.	
4304		Total Rotary Depth.	5-1/2" casing cemented at
			4303' w/ 175 sacks cement.

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 5 1951
 CONCRETION DEPT

I certify that this is the true and correct copy of the
 above log, to the best of my knowledge.

Subscribed and sworn to before me this 12th day of May,
 1955.

 Notary Public

My Commission Expires: 6-25-55