

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-009-19378-00-00

RECEIVED
STATE CORPORATION COMMISSION

JUL 25 1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name National Cooperative Refinery Association

Complete Address P. O. Box #6, Great Bend, Kansas 67530

Lease Name Dolechek Estate Well No. 5

Location NE SW SW Sec. 24 Twp. 16 Rge. (E) (W) 12

County Barton Total Depth 3351'

Abandoned Oil Well XX Gas Well Input Well ✓ SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 2:35 P Day 23 Month 7 Year 1974

The above well was plugged as follows:

Total depth 3351' 8 5/8 csg set at 272' cwc 185 sk.

5 1/2 csg set at 3326' cw 150 sk.

Filled 5 1/2 csg W/sd (3351'-3300') dumpad 5 sk cmt W/dump bailer. (3300'-3265')

Cutoff and recovered 520' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, -released 8 5/8 plug

and pumped 100 sk cmt by Allied Cementing Co.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 7/29/74

INV. NO. 9594-W