

KANSAS

M
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-145-01140 0000

RECEIVED
STATE CORPORATION COMMISSION
FEB 24 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company

Complete Address: 915 Union Nat'l Bldg., Wichita, Kansas

Lease Name Hutchinson "H" Well No. 5

Location NE NE SE Sec. 3 Twp. 23 Rge. 17 (E) (W) X

County Pawnee Total Depth 4318'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221 Great Bend, Kansas License No. 49

Operation Completed: Hour 1P Day 23 Month 2 Year 1969

The Above well was plugged as follows:

Total Depth 4318' 8 5/8 csg set at 242' CWC 175 sk.

5 1/2 csg set at 4317' cw 175 sk cmt.

5 1/2 csg PBTD 4306' with top perf. (4184)

Filled 5 1/2 csg W/sd (4160-4306) Dumped 5 sk cmt W/dump bailer. (4120-4160)

Cutoff and recovered 3120' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, Plug and 100 sk 50-50

poz cmt. W/6% total gel. Max pres. 300 lbs. SI pres. 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. Z. Messing
Well Plugging Supervisor

DATE 2/25/69

INV. NO. 9369-4