

KANSAS
STATE CORPORATION COMMISSION

15-145-01139-0000

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAR 24 1969
CONSERVATION DIVISION
Wichita, Kansas
3-24-69

Operator's Full Name Colorado Oil Company
Complete Address: 915 Union National Bldg., Wichita, Kansas 67202
Lease Name Hutchinson "H" Well No. 4
Location NW NW SE Sec. 3 Twp. 23 Rge. 17 (E) (W) XX
County Pawnee Total Depth 4264
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Forbes Casing Pulling
Address: Box 221 Great Bend, Kansas License No. 49
Operation Completed: Hour 3P Day 21 Month 3 Year 1969

The Above well was plugged as follows:

Total Depth 4264' 8 5/8 csg set at 251' 175 sk cmt.
5 1/2 csg set at 4263' cw 175 sk cmt.
5 1/2 csg PBTB 4235' with top perf. (4160)
Filled 5 1/2 csg W/sd (4150-4235) Dumped 5 sk cmt W/dump bailer. (4110-4150)
Cutoff and recov. 2000' of 5 1/2 csg.
Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.
Max pres 250 lbs. SI pres 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Russ G. Marant
Well Plugging Supervisor

DATE 3/24/69

INV. NO. 9511-W