

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
APR 11 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Colorado Oil Company 15-145-01138-0000

Complete Address: 915 Union National Bldg., Wichita, Kansas

Lease Name Hutchinson "F" Well No. 4

Location NW SW SW Sec. 3 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4293

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 2P Day 9 Month 4 Year 1969

The Above well was plugged as follows:

Total Depth 4293' 8 5/8 csg set at 257' cwc 175 sk.

5 1/2 csg set at 4292' cw 175 sk cmt.

5 1/2 csg PBTD 4279' with perf (4206-15)

Filled 5 1/2 csg W/sd (4190 - 4279) Dumped 5 sk cmt W/dump bailer. (4150 - 4190)

Cutoff and recov 3165' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

Max. pres. 500 lbs. SI pres. 400 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 4/11/69  
INV. NO. 9584-11