

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 14 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company 15-145-61136-0000

Complete Address: 915 Union National Bldg., Wichita, Kansas 67202

Lease Name Hutchinson "F" Well No. 2

Location NW NW SW Sec. 3 Twp. 23 Rge. 17 (E) (W) XX

County Pawnee Total Depth 4276

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 2:45P Day 9 Month 4 Year 1969

The Above well was plugged as follows:

Total Depth 4276' 8 5/8 csg set at 246' cwc 175 sk.

5 1/2 csg set at 4275 cw 175 sk cmt.

5 1/2 csg perf. (4178-4190)

Filled 5 1/2 csg W/sd (4160-4275) Dumped 5 sk cmt W/dump bailer. (4120-4160)

Cutoff and recov. 2600' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

Max. pres. 300 lbs. SI pres. 150 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo E. Massey
Well Plugging Supervisor

INVOICED

DATE 4/11/69
INV. NO. 9586-11