

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 3 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company 15-45-01135-8001

Complete Address: 915 Union Nat'l Bldg., Wichita, Kansas 67202

Lease Name Hutchinson "H" Well No. 6

Location C SE Sec. 3 Twp. 23 Rge. 17 (E) (W) X

County Pawnee Total Depth 4299

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling

Address: Box 221 Great Bend, Kansas License No. 49

Operation Completed: Hour 10:30A Day 28 Month 2 Year 1969

The Above well was plugged as follows:

Total Depth 4299' 8 5/8 csg set at 252' cwc 175 sk

5 1/2 csg set at 4298' cw 175 sk cmt.

5 1/2 csg PBTB 4268' With top perf. 4192'.

Filled 5 1/2 csg with sand (4175-4268) Dumped 5 sk cmt W/dump bailer. (4135-4175)

Shutoff and recovered 3202' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk commm

Cmt. Max. pres. 300 lbs. SI pres. 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Murray
Well Plugging Supervisor

DATE 3/4/69
INV. NO. 9418-4