

KANSAS

Handwritten mark

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 11 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company 15-145-01134-0000

Complete Address: 915 Union National Bldg., Wichita, Kansas 67202

Lease Name Hutchinson "F" Well No. 1

Location NW NE NW Sec. 3 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4275

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 6:15P Day 9 Month 4 Year 1969

The Above well was plugged as follows:

Total Depth 4275' 8 5/8 csg set at 247' cwc 175 sk.

5 1/2 csg set at 4275' cw 175 sk cmt.

5 1/2 csg PBTD 4235' and perf (4156-4159)

Filled 5 1/2 csg W/sd (4110-4235) Dumped 5 sk cmt W/dump bailer. (4100-4110)

Cutoff and recov. 3189' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

Max. pres. 500 lbs. SI pres. 500 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: L. J. Messing
Well Plugging Supervisor

DATE 4/11/69
INV. NO. 9587-4