

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
MAR 21 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Colorado Oil Company 15-445-01133-0000

Complete Address: 915 Union National Bldg., Wichita, Kansas 67202

Lease Name Hutchinson "F" Well No. 6

Location S/2 SW SW Sec. 3 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4315'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 4P Day 20 Month 3 Year 1969

The Above well was plugged as follows:

Total Depth 4315' 8 5/8 csg set at 243' cwc 175 sk.

5 1/2 csg set at 4314' cw 175 sk cmt.

5 1/2 csg PBTB 4228' and perf. (4198-4204)

Filled 5 1/2 csg W/sd (4180-4228) Dumped 5 sk cmt W/dump bailer. (4140-4180)

Shutoff and recov. 3290' of 5 1/2 csg.

Pumped thru 8 5/8 plug container 20 sk gel W/4 sk hulls, 50 sk hulls, plug and 100 sk

50-50 poz cmt W/6% total gel. Max pres. 500 lbs. SI pres 200 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Bio F. Massey
Well Plugging Supervisor

INVOICED

DATE 3-21-69

INV. NO. 9496-W