

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 11 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Colorado Oil Company 15-145-61132-0000

Complete Address: 915 Union Nat'l Bldg., Wichiat, Kansas 67202

Lease Name Hutchinson WF¹¹ Well No. 5

Location SE NW 5²⁰ SE SW Sec. 3 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4265

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 3:45P Day 9 Month 4 Year 1969

The Above well was plugged as follows:

Total Depth 4265' 8 5/8 csg set at 241' cwc 175 sk.

5 1/2 csg set at 4264' cw 175 sk cmt.

5 1/2 csg PBD 4174 with top perf. at 4158

Filled 5 1/2 csg W/sd (4150-4174) Dumped 5 sk cmt W/dump bailer. (4110-4150)

Cutoff and recovered 2866' of 5 1/2 csg

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

Max. pres. 350 lbs. SI pres. 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/11/69
INV. NO. 9583-W

Signed: Go Munnif
Well Plugging Supervisor