

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 21 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company 15.145-00306-0000

Complete Address: 915 Union National Bldg., Wichita, Kansas 67202

Lease Name Hutchinson "H" Well No. 1

Location NW NW NE Sec. 3 Twp. 23 Rge. (E) (W)17

County Pawnee Total Depth 4282

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221 Great Bend., Kansas License No. 49

Operation Completed: Hour 3:45P Day 18 Month 4 Year 1969

The Above well was plugged as follows:

Total Depth 4282' 8 5/8 csg set at 250' cwc 175 sk.

5 1/2 csg set at 4281' cw 175 sk cmt.

5 1/2 csg PPTD 4190' with top perf. (4168')

Filled 5 1/2 csg W/sd (4150-4190) Dumped 5 sk cmt W/dump bailer/(4110-4150)

Cutoff and recov. 3000' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

Max. pres. 250 lbs. SI pres. 100 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Len F. Mancy  
Well Plugging Supervisor

INVOICED

DATE 4/21/69

INV. NO. 9626-44