

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 14 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company 15-145-00297-0000

Complete Address: 915 Union National Bldg., Wichita, Kansas 67202

Lease Name Hutchinson "H" Well No. 2

Location SE SE NE Sec. 3 Twp. 23 Rge. 17 (E) (W) XX

County Pawnee Total Depth 4292

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling Inc.

Address: Box 221 Great Bend, Kansas License No. 49

Operation Completed: Hour 3P Day 12 Month 3 Year 1969

The Above well was plugged as follows:

Total Depth 4292' 8 5/8 csg set at 240' cwc 175 sk.

5 1/2 csg set at 4291' cw 175 sk cmt.

5 1/2 csg PBTB 4258' Top perf. 4206'

Filled 5 1/2 csg W/sd (4200-4258) Dumped 5 sk cmt W/dump bailer. (4160-4200)

Cutoff and recov. 3100' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

Max. pres. 500 lbs. SI pres. 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 3/14/69
INV. NO. 9457-11

Signed: [Signature]
Well Plugging Supervisor