

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 21 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Colorado Oil Company 15-145-01131-0000

Complete Address: 915 Union National Bldg., Wichita, Kansas 67202

Lease Name Hutchinson "H" Well No. 8

Location SE SE SE Sec. 3 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4315'

Abandoned Oil Well Gas Well Input Well SWD Well XX D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling, Inc.

Address: Box 221 Great Bend, Kansas License No. 49

Operation Completed: Hour 5P Day 19 Month 4 Year 1969

The Above well was plugged as follows:

Total Depth 4315' 8 5/8 csg set at 234' cwc 175 sk.

5 1/2 csg set at 4314' cw 175 sk cmt.

5 1/2 csg PBTD 4180' top perf. 3827'

Set 5 1/2 plug at 3800' Poured 10' sand (3790-3800) Dumped 5 sk cmt W/dump bailer. (3750-3790)

Cutoff and recov. 2700' of 5 1/2 csg.

Fumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

Max. pres. 400 lbs. SI pres. 400 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Geo F. Massey
Well Plugging Supervisor

INVOICED

DATE 4/21/69
INV. NO. 9627-W