

15.185.19494.0001

Form CP-3  
Rev. 6-26-62

*70*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

OCT 31 1963

CONSERVATION DIVISION  
Wichita, Kansas

10-31-63

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Petroleum Inc.

Complete Address: Route 2, Great Bend, Kansas

Lease Name Dell East Lansing K.C. Unit Tract 2 Well No. # 1

Location NW NW SE Sec. 8 Twp. 21 Rge. 13 (E) (W)

County Stafford Total Depth 3589

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Southwest Casing Pulling Co., Inc.

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 7:15PM Day 28th Month Oct. Year 1963

The Above well was plugged as follows:

214' of 8 5/8" surface pipe, cemented with 175 sacks. 3585' of 5 1/2" long  
string, cemented with 75 sacks. Top perferation 3453'. Bottom of hole  
was sanded to 3440', and cemented with 5 sacks. Due to water in hole and  
the short string of surface pipe, a squeeze job was decided. Hole was  
squeezed with 15 sacks of Gel Mud and 75 sacks of cement, through an  
8 5/8" swage, in the surface pipe. to a pressure of 100 lbs.  
2870' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

DATE 10/31/63

INV. NO. 8001-41

Signed: Archie Elving  
Well Plugging Supervisor