

15.185.01495.0001

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

NOV 7 1963

CONSERVATION DIVISION
Wichita, Kansas
7-7-63

Operator's Full Name Petroleum Inc.

Complete Address: Route 2, Great Bend, Kansas

Lease Name Dell East Lansing K.C. Unit Tract 1 Well No. # 1

Location SW SW NE Sec. 8 Twp. 21 Rge. 13 (E) (W) W

County Stafford Total Depth 3650

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Co. Inc.

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 12:30 PM Day 5th Month Nov. Year 1963

The Above well was plugged as follows:

203' of 8 5/8" surface pipe, cemented with 175 sacks. 3649' of 5 1/2" long
string, cemented with 75 sacks. Top perferation 3452'. Sand to 3440',
bottom cemented with 5 sacks. Due to the water problem and shortage of
surface pipe, a squeeze job was decided. 15 sacks of Gel-Mud and 75 sacks
cement was pumped into surface pipe, through an 8 5/8" swage, to a pressure
of 100 lbs.

3243' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

DATE 11/8/63
INV. NO. 8039-W

Signed: Archie Elving
Well Plugging Supervisor