

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County, Sec. 7 Twp. 21 Rge. 14 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW NW NE

Lease Owner Great Bend Pipe & Supply Company, Inc.

Lease Name Frey "A" Well No. 3

Office Address Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 3-18-64 19

Plugging completed 3-21-64 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elyng

Producing formation Depth to top Bottom Total Depth of Well 3722 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	883'	None
				5-1/2"	3720'	3271'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 3722', sanded hole to 3700' and dumped 5 sacks of cement @ 3700' with dump bailer. Pulled 5 1/2" casing, set rock bridge from 300' to 290' and dumped 25 sacks of cement. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

MAR 30 1964

3-30-64

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or owner/operator of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of March, 19 64

Milton J. Volin

My commission expires May 20, 1964

Notary Public.

15.185.01962.0000

THE VICKERS PETROLEUM CO., INC.

Frey Well #3
SW NW NE Sec. 7-21S-14W
Stafford County, Kansas

Casing Record:
8-5/8" O 883' w/400 ax
5-1/2" C 3706' w/75 ax

Commenced: November 2, 1950
Completed: December 5, 1950

Elevation: 1931 F.S.
Potential: Schometer 4986 BOPD
No water

LOG

Sand	0-40
Surface & sand	40-280
Shale & Sand	280-310
Sand	310-400
Sand & Shale	400-445
Red Bed & Red rock	445-690
Red Bed & Shale	690-880
Anhydrite	880-905
Red bed Shale & Shells	905-1380
Shale & Salt	1380-1610
Broken Lime	1610-1745
Lime & Shale	1745-1875
broken Lime & Sand	1875-2010
Lime & Sand	2010-2080
Lime & Shale	2080-2575
Shale & Lime	2575-2765
Lime & Shale	2765-2965
Lime	2965-3100
Lime & Shale	3100-3285
Shale	3285-3357
Lime & Shale	3357-3625
Chert	3625-3658
Shale	3658-3703
Dolomite	3703-3714 RTD

BST 3483-3493. Open 20 min.
Recovered 30' Lrlg. mud. 860# B.H.I.

Cable Tools:
Drill plug, clean out to 3714
Swab 10 BOPH one hour
Drill deeper 3716, Swab 15 BOPH one hour
Fill up 14 hrs. 3300' oil
Drill deeper to 3718 TD. Swab 29 BOPH one hour
Run tubing & Acidize w/2000 gal.
Swab 37 1/2 BOPH one hour

Tops:	
Heebner	3254
Brown Lime	3357
Lansing	3375
Viola	3625
Simpson	3658
Arbuckle	3703

RECEIVED
STATE CORPORATION COMMISSION

MAR 24 1964

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that this log is true and correct to the best of my knowledge and belief.

The Vickers Petroleum Co., Inc.

By: W.P. Summers

Sworn and subscribed to before me this 12th day of December, 1950.

Allen J. Denton
Notary Public

My commission expires Aug. 13, 1953.