

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Stafford County, Sec. 12 Twp. 21S Rge. (E) 14 (W)

Location as "NE/CNW%SW%" or footage from lines NW NW NE

Lease Owner Tennessee Gas Transmission Company

Lease Name Gary C. Brown Well No. 1

Office Address P.O. Box 163, Great Bend Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 26 19 57

Application for plugging filed July 9 19 57

Application for plugging approved (Oral) June 25 19 57

Plugging commenced June 25 19 57

Plugging completed June 25 19 57

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R.M. Brundage

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3743 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" OD	393	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 250',
Set plug at 250' w/ 1/2 sack hulls and
cemented with 20 sacks through drill pipe.
Filled hole with heavy mud to 20'
Set plug at 20' w/ 1/2 sack hulls and cemented
to cellar with 5 sacks.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor _____

Address _____

STATE OF KANSAS, COUNTY OF RICE, ss.
Glen E. Armour (employee of owner) ~~owner or operator~~

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glen E. Armour

(Address) _____

SUBSCRIBED AND SWORN TO before me this 10 day of July, 19 57

My commission expires May 20 1958

Vincent O. Gray
Notary Public.
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC 12 T 21 R 14W
BOOK PAGE 23 LINE 30

JUL 11 1957
CONSERVATION DIVISION
Wichita, Kansas

15.185.00575.0000

GARY C. BROWN #1

NW/4 NW/4 NE/4 of Section 12-21S-14W Stafford County, Kansas

Rigged up Rotary Tools 6/15/57	Ran 13 Jts. (393') 8 5/8" OD 24#
Tore down Rotary Tools 6/25/57	surface pipe set @ 390'. Cemented w/250 sacks common cement, 2% CC

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Clay, sand & shale	0'	390'
Sand, shale & redbed	390	805
Anhydrite	805	830
Shale w/shell streaks	830	1140
Shale & shells	1140	1615
Shale, shells & salt	1615	1670
Lime & shale	1670	3265
Shale	3265	3342
Lime	3342	3600
Lime & chert	3600	3693
Lime	3693	3743 T.D.

I, Don S. Packer, do hereby certify that the foregoing logs are true and correct, to the best of my knowledge and belief.

Don S. Packer

Subscribed and sworn to before me this 26th day of June, 1957

Jane Swamy

Notary Public

My commission expires: July 29, 1957

RECEIVED
STATE CORPORATION COMMISSION
JUL 11 1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 12 T. 21 R. 14W
BOOK PAGE 23 LINE 38