


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rice County, Sec. 17 Twp. 21S Rge. 8 (~~EA~~) (W)
Location as "NE/CNW/SW" or footage from lines. NW NW NW
Lease Owner Francis Oil & Gas, Inc.
Lease Name Moore Well No. 11
Office Address 905 Palace Building, Tulsa, Oklahoma 74103
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed April 26 19 67
Application for plugging filed April 26 19 67
Application for plugging approved April 26 19 67
Plugging commenced April 26, 10:00 a.m. 19 67
Plugging completed April 26, 12:00 noon 19 67
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman, Holyrood, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3452 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	236'	8-5/8	X	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 230', Howco plug, 1/4 sack hulls, mixed 25 sacks cement thru open end of drill pipe, filled hole with heavy mud to 40', Howco plug, 1/2 sack hulls, 10 sacks cement, 2 sacks cement in rat hole.

RECEIVED
MAY 1 1967
CONSERVATION DIVISION
Wichita, Kansas

5-4-67

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sterling Drilling Company
Address Box 129, Sterling, Kansas 67579

STATE OF KANSAS, COUNTY OF RICE, ss.
F. A. Wuellner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) F. A. Wuellner
Box 129, Sterling, Kansas F. A. Wuellner
(Address)

SUBSCRIBED AND SWORN to before me this 3rd day of May, 1967

Bernard Laudermilk
Bernard Laudermilk, Notary Public.

My commission expires _____

BERNARD LAUDERMILK, Notary Public
Commission Expires January 22, 1970

STERLING DRILLING COMPANY
Sterling, Kansas

WELL LOG ----- MOORE #1
LOCATED: NW NW NW Section 17-21S-8W, Rice County, Kansas

OWNER: Francis Oil & Gas, Inc.
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: April 19, 1967
COMPLETED: April 26, 1967

ROTARY TOTAL DEPTH: 3452'

LOG

0 - 85	Sand & Gravel	
85 - 240	Red Bed	
240 - 400	Shale	
400 - 2905	Shale & Lime	
2905 - 3330	Lime	
3330 - 3452	Lime & Shale	T.D.

CASING RECORD

Run 5 joints 8-5/8" 16# new seamless casing, 224' pipe set at 236' K.B., cemented with 225 sacks Sun Set cement with MA-5. Plug was down at 1:10 a.m..

Plugged as follows: Filled hole with heavy mud to 230', Howco plug, 1/4 sack hulls, mixed 25 sacks cement thru open end of drill pipe, filled hole with heavy mud to 40', Howco plug, 1/2 sack hulls, 10 sacks cement. 2 sacks cement in rat hole. Finish plugging at 12:00 noon 4-26-67. Gilbert Toman, State Plugger.

RECEIVED
OIL & GAS CORPORATION COMMISSION
MAY 4 1967
CONSERVATION DIVISION
Wichita, Kansas