

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15.159.20945.0000

LEASE NAME Dymond #1

WELL NUMBER _____

SPOT LOCATION C NE NW SW

SEC. 15 TWP. 21 S RGE. 8 W (E) or (W)

COUNTY Rice

Date Well Completed _____

Plugging Commenced 1/27/84

Plugging Completed 3/21/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Hummon Corporation

ADDRESS 400 One Main Place, Wichita, Ks. 67202

PHONE # (316) 263-8521 OPERATORS LICENSE NO. #5050

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Salina

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom _____ T.D. 3420'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8.5/8	267.12'	none
				4 1/2"	3419'	2847'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Blew well down, & pumped 50 sacks cement to 3212'. Shot pipe at 2847'.
Pulled 67 joints of 4 1/2". Killed gas with 47 sacks gel, 50 sacks weight mud
down casing. Found fluid at 960'. Ran 15 gel, & 125 sacks 50/50 poz 4% gel
3% c.c.
Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

RECEIVED
STATE CORPORATION COMMISSION
DESIGN

MAR 26 1984

SUBSCRIBED AND SWORN TO before me this 23rd day of March, 19 84

Wichita, Kansas
My Commission expires:



Irene Hoover
Notary Public

15.159.20945.0000

DRILLERS LOG

No. 1 Dymond

CASING RECORD:	COMPANY: Hummon Corporation	DESCRIPTION:
8 5/8" @ 267.12' w/120 sx cement	CONTRACTOR: Red Tiger Drilling Company	C NE/4 NW/4 SW/4 Sec. 15-T21S-R8W Rice County, Kansas
4 1/2" @ 3,419' w/125 sx cement	COMMENCED: June 17, 1980	
	COMPLETED: June 23, 1980	
TOTAL DEPTH: 3,420'		ELEVATION: 1,645' KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	158	
Sand & Clay	158	191	
Red Bed & Green Shale	191	274	
Red Bed & Shale	274	1079	
Shale & Lime	1079	1615	
Lime & Shale	1615	2010	
Lime	2010	2390	
Shale & Lime	2390	2630	
Lime & Shale	2630	2902	
Lime	2902	3325	
Chert	3325	3351	
Shale.w/Lime	3351	3375	
Shale	3375	3420	
RTD		3420	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett
Gloria Fawcett

Subscribed and sworn to before me this 26th day of June, 1980.

Joyce A. Hagermann
Notary Public