

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-159-21,078-0000

LEASE NAME Wilkey #1

WELL NUMBER \_\_\_\_\_

SPOT LOCATION C SE SW NE

SEC. 15 TWP. 21s RGE. 8w (E) of W

COUNTY Rice

Date Well Completed \_\_\_\_\_

Plugging Commenced 5/24/84

Plugging Completed 5/30/84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Hummon Corporation

ADDRESS 400 One Main Place, Wichita, Ks. 67202

PHONE # (316) 263-8521 OPERATORS LICENSE NO. # 5050

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Salina

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3384'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	279.82'	none
				4 1/2"	3382'	2914'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Pumped bottom with 1/2 sacks hulls, & 50 sacks cement, pushed plug to 3150'. Shot pipe at 2900' & pulled 72 joints of pipe. Plugged well with 3 hulls, 10 gel, 2 hulls, 8 5/8 plug & 125 sacks 50/50 poz 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss. **RECEIVED**  
STATE CORPORATION COMMISSION

R. Darrell Kelso (employee of operator) or  
(operator) of above-described well, being first duly sworn on oath, says: That JUN 04 1984  
I have knowledge of the facts, statements, and matters herein contained and  
the log of the above-described well as filed that the same are true and  
correct, so help me God. CONSERVATION DIVISION  
Wichita, Kansas

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 1st day of June, 1984



My Commission expires \_\_\_\_\_

Irene Hoover  
NOTARY PUBLIC

DRILLERS LOG

No. 1 Wilkey

CASING RECORD:	COMPANY:	Hummon Corporation	DESCRIPTION:
8 5/8" @ 279.82' w/225 sx cement	CONTRACTOR:	Red Tiger Drilling Company	SE/4 SW/4 NE/4 Sec. 15-T21S-R8W Rice County, Kansas
4 1/2" @ 3,382' w/100 sx cement	COMMENCED:	February 6, 1981	
	COMPLETED:	February 12, 1981	
TOTAL DEPTH: 3,384'			ELEVATION: 1,639' KB

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Sand	0	168
Red Bed & Shale	168	1065
Shale & Lime	1065	1155
Lime & Shale	1155	1680
Lime w/Shale Streaks	1680	2000
Lime & Shale	2000	2540
Lime, Shale & Sand	2540	2835
Lime & Shale	2835	3055
Lime	3055	3324
Mississippi	3324	3355
Lime	3355	3384
RTD		3384

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Gloria Fawcett  
Gloria Fawcett

Subscribed and sworn to before me this 17th day of February, 1981.

Joyce A. Baer  
Notary Public



RECEIVED  
STATE CORPORATION COMMISSION  
APR 24 1984  
CONSERVATION DIVISION  
Wichita, Kansas