

STATE OF KANSAS
ATE CORPORATION COMMISSION
D S. Market, Room 2078
Topeka, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-159-00002-0000 ⁰⁰⁰¹

LEASE NAME Bell

WELL NUMBER #1

2970 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 15 TWP. 21S RGE. 8W (E) or (W)

COUNTY Rice

Date Well Completed _____

Plugging Commenced 1-21-98

Plugging Completed 1-23-98

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

EASE OPERATOR BEREXCO, INC.

ADDRESS P.O. Box 723 Hays, Kansas 67601

PHONE# (913) 628-6101 OPERATORS LICENSE NO. 5363

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3733'

show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	215'	none
				4-1/2"	3412'	2400'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug material was used, state the character of same and depth placed, from _____ feet to _____ feet. Plugged off bottom with sand to 3029' and 4 sks. cement. Shot casing loose @ 2400', pulled up to 1100', pumped 35 sks. cement and 100# hulls, pulled to 650', pumped 35 sks. cement and 100# hulls, pulled up to 265' and circulated 120 sks. cement to surface, 60/40 pos, 4% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Berexco, Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 4th day of February, 1998

[Signature]
Notary Public

My Commission Expires: August 24, 2001

